

CONTRACT NO. 72680

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
			80% FEDERAL 20% STATE	ROADWAY I000-2A	WETLAND MITIGATION Y077	CULVERT STA 960+46.00 X028-2A	BRIDGE SEC 34-4B STA 973+28.00 X081-2A	BRIDGE SEC 34-4B-1 STA 1153+07.72 X071-2A	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
54202959	PIPE CULVERTS, TYPE 4 RCCP 24"	FOOT	58	58						
54203007	PIPE CULVERTS, TYPE 4 RCCP 72"	FOOT	336	336						
54203589	PIPE CULVERTS, TYPE 5 RCCP 24"	FOOT	64	64						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1						
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1						
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2						
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	18	18						
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	12	12						
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2						
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2	2						
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2	2						
54215442	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 42"	EACH	4	4						
54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	2	2						
54215454	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 54"	EACH	2	2						
54215472	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 72"	EACH	2	2						
54215547	METAL END SECTIONS 12"	EACH	2	2						
54215559	METAL END SECTIONS 24"	EACH	16	16						
54215571	METAL END SECTIONS 36"	EACH	2	2						
54217680	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER	EACH	8	8						
54217690	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 24" RISER	EACH	1	1						
5421D015	PIPE CULVERTS, CLASS D, TYPE 1, 15" (TEMPORARY)	FOOT	148	148						
5421D018	PIPE CULVERTS, CLASS D, TYPE 1, 18" (TEMPORARY)	FOOT	126	126						
5422D030	PIPE CULVERTS, CLASS D, TYPE 2, 30" (TEMPORARY)	FOOT	44	44						

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**FAP ROUTE 315
SUMMARY OF QUANTITIES**

DRAWN BY TJD
DATE 1/31/06
CHECKED BY JRB