

CONTRACT NO. 72680

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
			80% FEDERAL 20% STATE	ROADWAY 1000-2A	WETLAND MITIGATION Y077	CULVERT STA 960+46.00 X028-2A	BRIDGE SEC 34-4B STA 973+28.00 X081-2A	BRIDGE SEC 34-4B-1 STA 1153+07.72 X071-2A	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E	
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2	2							
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2	2							
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	1,500	1,500							
61100605	MISCELLANEOUS CONCRETE	CU YD	50	50							
61139900	STORM SEWERS, SPECIAL 6"	FOOT	4,000	4,000							
61140000	STORM SEWERS, SPECIAL 8"	FOOT	1,000	1,000							
61140100	STORM SEWERS, SPECIAL 10"	FOOT	1,000	1,000							
61140200	STORM SEWERS, SPECIAL 12"	FOOT	1,000	1,000							
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	4,337.5	4,337.5							
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	16	16							
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	18	18							
63200310	GUARDRAIL REMOVAL	FOOT	1,949	1,949							
63500105	DELINEATORS	EACH	68	68							
64200105	SHOULDER RUMBLE STRIPS	FOOT	84,972	84,972							
66411900	TEMPORARY FENCE	FOOT	2,000	2,000							
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	167	167							
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	6	6							
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	23	23							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30							
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	30	30							
67100100	MOBILIZATION	L SUM	1	1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1							

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**FAP ROUTE 315
SUMMARY OF QUANTITIES**

DRAWN BY TJD
DATE 1/31/06
CHECKED BY JRB