

ROUTE NO. TOTAL SHEETS FAP 315 452 188 HANCOCK FED. ROAD DIST. NO. 7 ILLINOIS

* 34-4B

CONTRACT NO. 72680

SHEET NO. 11

21 SHEETS

INTERIOR BEAM MOMENT TABLE		
		0.5 Span
I	(in4)	213,715
I'	(in4)	481,649
I' Sb Sb' St St'	(in³)	8 , 559
Sb'	(in³)	12,507
S _t	(in³)	7 , 362
St'	(in³)	31,094
P	(k/')	1.222
MФ	('k)	1,379
5₽	(k/')	0.458
Ms₽	('k)	517
М4_	('k)	804
M (Imp)	('k)	183

INTERIOR BEAM REACTION TABLE		
		Abut.
R₽	(k)	58 . 0
Rs₽	(k)	21.8
R4	(k)	36.4
Imp.	(k)	8.3
R (Total)	(k)	<i>124.</i> 5

 $\it I$ and $\it I'$ are the moment of inertia and composite moment of inertia of the beam section.

 S_b and S_b ' are the non-composite and composite section modulus for the bottom fiber of the prestressed

S₁ and S₁' are the non-composite and composite section modulus for the top fiber of the prestressed

 $M_{\mathcal{P}}$ is the moment due to dead loads on the noncomposite prestressed beam.

 $\mathit{Ms}_{\it p}$ is the moment due to dead loads on the composite section. Mi is the moment due to live load on the composite section.

M (Imp) is the moment due to live load impact on the composite section.

> FRAMING PLAN FAP ROUTE 315 OVER PRAIRIE CREEK SECTION 34-4B HANCOCK COUNTY STATION 973+28.00 STR. NO. 034-0506 (WBL) STR. NO. 034-0507 (EBL)

HUTCHISON ENGINEERING, INC. JACKSONVILLE, ILLINOIS Date: January 31, 2006