

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(86-10IRS-2	SCOTT	52	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVEMENT PATCHING CLASS B												
PATCH NUMBER	LOCATION		LENGTH (FT)	WIDTH (FT)	CLASS B PATCH TY II 8"	CLASS B PATCH TY III 8"	CLASS B PATCH TY II 12"	CLASS B PATCH - EXPANSION JOINT (FT)	DEFORMED BARS - EXPANSION JOINT (EACH)	DOWEL BARS 1 1/2" (EACH)	SAW CUTS (FT)	PAVEMENT FABRIC (SQ YD)
	STATION TO	STATION DESCRIPTION			(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(EACH)	(FT)	(SQ YD)
I-72 EASTBOUND												
B1	103+25.0	- 103+31.0	DRIVING LANE	6.0	12.0			8.0		20.0	60.0	
B2	103+25.0	- 103+31.0	PASSING LANE	6.0	12.0			8.0		20.0	60.0	
B3	106+83.0	- 106+89.0	DRIVING LANE	6.0	12.0			8.0		20.0	60.0	
B4	106+83.0	- 106+89.0	PASSING LANE	6.0	12.0			8.0		20.0	60.0	
I-72 WESTBOUND												
B5	103+55.0	- 103+61.0	DRIVING LANE	6.0	12.0			8.0		20.0	60.0	
B6	103+55.0	- 103+61.0	DRIVING LANE	6.0	12.0			8.0		20.0	60.0	
B7	107+13.0	- 107+19.0	DRIVING LANE	6.0	12.0			8.0		20.0	60.0	
B8	107+13.0	- 107+19.0	DRIVING LANE	6.0	12.0			8.0		20.0	60.0	
RAMP A												
B9	112+84.0	- 112+96.0		12.0	16.0		21.3		16.0	28.0	14.0	88.0 21.3
B10	128+00.0	- 128+06.0		6.0	16.0	10.7				28.0	76.0	
RAMP B												
B11	222+00.0	- 222+06.0		6.0	16.0	10.7				28.0	76.0	
B12	238+14.0	- 238+26.0		12.0	16.0		21.3		16.0	28.0	14.0	88.0 21.3
RAMP C												
B13	339+41.0	- 339+29.0		12.0	16.0		21.3		16.0	28.0	14.0	88.0 21.3
B14	324+00.0	- 324+06.0		6.0	16.0	10.7				28.0	76.0	
RAMP D												
B15	413+16.0	- 413+04.0		12.0	16.0		21.3		16.0	28.0	14.0	88.0 21.3
B16	428+25.0	- 428+31.0		6.0	16.0	10.7				28.0	76.0	
OLD 36												
B17	NW Quad SN 086-0027	End of App. Pvmf	12.0	14.0		18.7		14.0	24.0	12.0	80.0	18.7
B18	SW Quad SN 086-0027	End of App. Pvmf	12.0	14.0		18.7		14.0	24.0	12.0	80.0	18.7
B19	NE Quad SN 086-0027	End of App. Pvmf	12.0	14.0		18.7		14.0	24.0	12.0	80.0	18.7
B20	SE Quad SN 086-0027	End of App. Pvmf	12.0	14.0		18.7		14.0	24.0	12.0	80.0	18.7
	OLD 36 Estimated Quantities					42.0				140.0	420.0	
	I-72 SUBTOTAL:					42.7	85.3	64.0	64.0	112.0	328.0	1,136.0 85.3
	OLD 36 SUBTOTAL:					42.0	74.7	0.0	56.0	96.0	188.0	740.0 74.7
	CLASS B SUBTOTAL:					84.7	160.0	64.0	120.0	208.0	516.0	1,876.0 160.0

PLOT DATE : #DATES
 FILE NAME : #FILE#
 PLOT SCALE : #SCALE#
 REFERENCE : #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 72
 SECTION (86-10IRS-2
 SCOTT COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____