

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	186-10RS-2	SCOTT	52	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

POLYUREA PAVEMENT MARKING TYPE II - LINE 8"			
LOCATION	DESCRIPTION	COLOR	POLYUREA PVT MK TY II - 8" (FOOT)
STATION TO STATION			
RAMP A			
125+31.0	WRONG WAY ARROW	WHITE	36.5
126+56.0	WRONG WAY ARROW	WHITE	36.5
127+40.0 - 127+81.0	ISLAND - RT TURNLANE	WHITE	58.9
127+40.0 - 127+81.0	ISLAND - LT TURNLANE	WHITE	44.0
127+81.0 - 127+81.0	ISLAND	WHITE	56.9
RAMP C			
326+98.0	WRONG WAY ARROW	WHITE	36.5
325+76.0	WRONG WAY ARROW	WHITE	36.5
324+89.0 - 324+48.0	ISLAND - RT TURNLANE	WHITE	58.9
324+89.0 - 324+48.0	ISLAND - LT TURNLANE	WHITE	44.0
324+48.0 - 324+48.0	ISLAND	WHITE	56.9
I-72 SUBTOTAL:			465.6
OLD 36 SUBTOTAL:			0.0
GRAND TOTAL:			465.6

PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LINE 5"			
LOCATION	DESCRIPTION	COLOR	PREF PL PVT MK TY A - 5" (FOOT)
STATION TO STATION			
I-72			
0+35.0 - 104+28.0	EB CENTERLINE (SKIP DASHES)	WHITE	2,598.3
104+58.0 - 0+35.0	WB CENTERLINE (SKIP DASHES)	WHITE	2,605.8
I-72 SUBTOTAL:			5,204.0
OLD 36 SUBTOTAL:			0.0
GRAND TOTAL:			5,204.0

POLYUREA PAVEMENT MARKING TYPE II - LINE 12"			
LOCATION	DESCRIPTION	COLOR	POLYUREA PVT MK TY II - 12" (FOOT)
STATION			
RAMP A			
127+50.0	ISLAND	WHITE	12.1
127+63.0	ISLAND	WHITE	3.8
127+70.0	ISLAND	WHITE	27.8
127+76.0	ISLAND	WHITE	14.0
RAMP C			
324+52.0	ISLAND	WHITE	12.1
324+58.0	ISLAND	WHITE	14.5
324+62.0	ISLAND	WHITE	8.8
324+65.0	ISLAND	WHITE	3.6
324+77.0	ISLAND	WHITE	10.9
I-72 SUBTOTAL:			107.6
OLD 36 SUBTOTAL:			0.0
GRAND TOTAL:			107.6

PREFORMED PLASTIC PAVEMENT MARKING, TY A - LN 8"			
LOCATION	DESCRIPTION	COLOR	PREF PL PVT MK TY A - 8" (FOOT)
STATION TO STATION			
I-72			
9+21.0 - 13+00.0	EB RT EDGE LINE	WHITE	379.0
37+91.0 - 42+38.0	EB RT EDGE LINE	WHITE	447.0
43+07.0 - 39+30.0	WB RT EDGE LINE	WHITE	377.0
14+26.0 - 9+91.0	WB RT EDGE LINE	WHITE	435.0
RAMP A			
109+21.0 - 112+99.0	LT EDGE LINE	WHITE	378.0
RAMP B			
237+93.0 - 242+38.0	LT EDGE LINE	WHITE	445.0
RAMP C			
343+07.0 - 339+29.0	LT EDGE LINE	WHITE	378.0
RAMP D			
414+23.0 - 409+91.0	LT EDGE LINE	YELLOW	432.0
I-72 SUBTOTAL:			3,271.0
OLD 36 SUBTOTAL:			0.0
GRAND TOTAL:			3,271.0

PREFORMED PLASTIC PAVEMENT MARKING, TY A - LN 24"			
LOCATION	DESCRIPTION	COLOR	PREF PL PVT MK TY A - 24" (FOOT)
STATION			
RAMP A			
127+54.0	LT STOPBAR	WHITE	18.0
127+57.0	RT STOPBAR	WHITE	18.0
RAMP C			
324+71.0	LT STOPBAR	WHITE	18.0
324+71.0	RT STOPBAR	WHITE	18.0
I-72 SUBTOTAL:			72.0
OLD 36 SUBTOTAL:			0.0
GRAND TOTAL:			72.0

PLOT DATE: 2/22/2006
 FILE NAME: c:\projects\186-10RS-2\186-10RS-2.dwg
 PLOT SCALE: 1/8"=1'-0"
 REFERENCE: SHEETS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 72
 SECTION 186-10RS-2
 SCOTT COUNTY
 VERT. SCALE: DATE: DRAWN BY: CHECKED BY: