

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	186-10RS-2	SCOTT	52	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SHORT-TERM PAVEMENT MARKING			
LOCATION	DESCRIPTION	COLOR	SHORT-TERM PAVEMENT MARKING (FOOT)
STATION TO STATION			
I-72			
0+35.0 - 104+28.0	EB RT EDGE (2' EVERY 200')	WHITE	103.9
0+35.0 - 104+28.0	EB LT EDGE (2' EVERY 200')	YELLOW	103.9
104+58.0 - 0+35.0	WB RT EDGE (2' EVERY 200')	WHITE	104.2
104+58.0 - 0+35.0	WB LT EDGE (2' EVERY 200')	YELLOW	104.2
0+35.0 - 104+28.0	EB CENTERLINE (4' EVERY 40')	WHITE	1,039.3
104+58.0 - 0+35.0	WB CENTERLINE (4' EVERY 40')	WHITE	1,042.3
9+21.0 - 9+71.0	EB RT EDGE LINE (SOLID)	WHITE	50.0
41+88.0 - 42+38.0	EB RT EDGE LINE (SOLID)	WHITE	50.0
43+07.0 - 43+57.0	WB RT EDGE LINE (SOLID)	WHITE	50.0
10+41.0 - 9+91.0	WB RT EDGE LINE (SOLID)	WHITE	50.0
RAMP A			
106+37.0 - 127+00.0	RT EDGE LINE (4' EVERY 40')	WHITE	206.3
109+21.0 - 109+71.0	LT EDGE LINE (SOLID)	WHITE	50.0
109+71.0 - 127+00.0	LT EDGE LINE (4' EVERY 40')	YELLOW	172.9
RAMP B			
224+50.0 - 249+88.0	RT EDGE LINE (4' EVERY 40')	WHITE	253.8
224+50.0 - 241+88.0	LT EDGE LINE (4' EVERY 40')	YELLOW	173.8
241+88.0 - 242+38.0	LT EDGE LINE (SOLID)	WHITE	50.0
RAMP C			
345+91.0 - 325+25.0	RT EDGE LINE (4' EVERY 40')	WHITE	206.6
343+07.0 - 342+57.0	LT EDGE LINE (SOLID)	WHITE	50.0
342+57.0 - 325+25.0	LT EDGE LINE (4' EVERY 40')	YELLOW	173.2
RAMP D			
428+00.0 - 402+40.0	RT EDGE LINE (4' EVERY 40')	WHITE	256.0
428+00.0 - 409+41.0	LT EDGE LINE (4' EVERY 40')	YELLOW	185.9
409+41.0 - 409+91.0	LT EDGE LINE (SOLID)	WHITE	50.0
OLD US 36			
344+25.0 - 352+14.0	RT EDGE LINE (4' EVERY 100')	WHITE	31.6
353+54.0 - 359+49.0	RT EDGE LINE (4' EVERY 100')	WHITE	23.8
361+02.0 - 374+42.0	RT EDGE LINE (4' EVERY 100')	WHITE	53.6
376+03.0 - 386+03.0	RT EDGE LINE (4' EVERY 100')	WHITE	40.0
386+03.0 - 383+00.0	LT EDGE LINE (4' EVERY 100')	WHITE	12.1
381+59.0 - 375+83.0	LT EDGE LINE (4' EVERY 100')	WHITE	23.0
374+30.0 - 360+90.0	LT EDGE LINE (4' EVERY 100')	WHITE	53.6
359+29.0 - 344+25.0	LT EDGE LINE (4' EVERY 100')	WHITE	60.2
344+25.0 - 356+09.0	CENTERLINE (4' EVERY 40')	YELLOW	236.8
379+80.0 - 386+03.0	CENTERLINE (4' EVERY 40')	YELLOW	124.6
	I-72 SUBTOTAL:		4,526.4
	OLD 36 SUBTOTAL:		659.3
	GRAND TOTAL:		5,185.7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 72
 SECTION 186-10RS-2
 SCOTT COUNTY

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY