

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(86-10IRS-2)	SCOTT	52	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

MAINLINE RESURFACING

LOCATION	LENGTH	PVT WIDTH	PVT AREA	POLYMER BIT CONC SURF CSE, SUPER MIX "D" N90 (1.5" TH.)	BIT CONC SURF CSE, SUPER MIX "C" N50 (1.5" TH.)	POLY LEVEL BIND (MM) SUPER N 90 (1" THICK.)	POLYMER BIT CONC BIND CSE, SUPER IL-19.0 N90 (2.25" TH.)	LEVEL BINDER (MM) SUPER N50 (1" THICK.)	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
STATION TO STATION	( FT )	( FT )	( SQ YD )	( TON )	( TON )	( TON )	( TON )	( TON )	( TON )	( TON )	( TON )
OLD US 36 NORTHBOUND											
386+96.5 - 383+00.0	396.5	12	529		44.4			29.6	0.20	1.1	
383+00.0 - 379+80.0	320.0	12 to 15	480		40.3			26.9	0.18	1.0	
379+80.0 - 376+08.0	372.0	17 to 14	641		53.8			35.9	0.24	1.3	
376+08.0 - 374+58.0	150.0	14	233		19.6			13.1	0.09	0.5	
374+58.0 - 373+23.0	135.0	VARIES	269*		22.6			15.1	0.10	0.5	
373+23.0 - 368+95.5	427.5	14	665		55.9			37.2	0.25	1.3	
366+36.5 - 366+28.5	8.0	14	12		1.0			0.7	0.00	0.0	
366+28.5 - 363+58.5	270.0	14 to 26	600		50.4			33.6	0.23	1.2	
363+58.5 - 361+58.5	200.0	26	578		48.5			32.4	0.22	1.2	
361+58.5 - 360+27.0	131.5	VARIES	373*		31.3			20.9	0.14	0.7	
360+27.0 - 354+29.0	598.0	14	930		78.1			52.1	0.35	1.9	
354+29.0 - 351+30.0	299.0	18 to 12	498		41.9			27.9	0.19	1.0	
351+30.0 - 344+50.0	680.0	12	907		76.2			50.8	0.34	1.8	
I-72 SUBTOTAL:				5,989.5	0.0	791.0	7,199.8	0.0	27.1	142.6	13,980.3
OLD 36 SUBTOTAL:				0.0	1,115.3	0.0	0.0	743.5	5.0	26.6	0.0
GRAND TOTAL:				5,989.5	1,115.3	791.0	7,199.8	743.5	32.1	169.2	13,980.3

\* AREA FROM CAD.

CONCRETE CURB & GUTTER AND CONCRETE MEDIAN

LOCATION	COMB CC&G REMOVAL	CONC MEDIAN SURFACE REMOVAL	COMB CC&G, TY B-6.24	COMB CC&G, TY B-6.06	PCC RAMPED MEDIAN TERMINAL	CONC MEDIAN SURFACE, 4"	PRISMATIC CURB REFLECTORS
STATION, QUAD, OR ISLAND	( FOOT )	( SQ FT )	( FOOT )	( FOOT )	( EACH )	( SQ FT )	( EACH )
RAMP A							
ISLAND ( RAMP A @ OLD 36 )	55.4	142.2	33.7	21.7		142.2	11
RAMP C							
ISLAND ( RAMP C @ OLD 36 )	55.4	142.2	33.7	21.7		142.2	11
OLD US 36							
360+71.00	13.3	22.3			1		
361+29.00 - 362+08.00	156.8	274.9					
361+59.00 - 362+08.00				87.1	1	121.6	10
373+23.00 - 373+71.00	156.7	275.4					
373+23.00 - 374+02.00				87.1	1	121.6	10
374+55.00	13.3	22.1			1		
I-72 SUBTOTAL:	110.8	284.4	67.4	43.4	0.0	284.4	22.0
OLD 36 SUBTOTAL:	340.1	594.7	0.0	174.2	4.0	243.2	20.0
GRAND TOTAL:	450.9	879.1	67.4	217.6	4.0	527.6	42.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP 72  
 SECTION (86-10IRS-2)  
 SCOTT COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = \$DATE\$  
 FILE NAME = \$FILE\$  
 PLOT SCALE = \$SCALE\$  
 REFERENCE = \$REF\$