

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(86-10IRS-2	SCOTT	52	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUB-SURFACE DRAINAGE SCHEDULE

LOCATION	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS - 4" (SPECIAL)	CONCRETE HEADWALLS	SHOULDER REMOVAL & REPLACEMENT 5"
STATION TO STATION	( FT )	( FT )	( EACH )	( FT )
I-72 EASTBOUND & WESTBOUND				
30+00.0		64.0	4.0	32.0
30+00.0 - 35+00.0	2000.0			2000.0
35+00.0		32.0	2.0	32.0
35+00.0 - 40+00.0	1000.0			1000.0
40+00.0		64.0	4.0	32.0
40+00.0 - 45+00.0	2000.0			2000.0
45+00.0		64.0	4.0	32.0
45+00.0 - 50+00.0	2000.0			2000.0
50+00.0		64.0	4.0	32.0
50+00.0 - 55+00.0	2000.0			2000.0
55+00.0		64.0	4.0	32.0
55+00.0 - 60+00.0	2000.0			2000.0
60+00.0		64.0	4.0	32.0
60+00.0 - 65+00.0	2000.0			2000.0
65+00.0		64.0	4.0	32.0
65+00.0 - 70+00.0	2000.0			2000.0
70+00.0		64.0	4.0	32.0
70+00.0 - 75+00.0	2000.0			2000.0
75+00.0		64.0	4.0	32.0
75+00.0 - 80+00.0	2000.0			2000.0
80+00.0		64.0	4.0	32.0
80+00.0 - 83+00.0	1200.0			1200.0
83+00.0		128.0	8.0	32.0
83+00.0 - 86+00.0	1200.0			1200.0
86+00.0		64.0	4.0	32.0
86+00.0 - 91+00.0	2000.0			2000.0
91+00.0		64.0	4.0	32.0
91+00.0 - 96+00.0	2000.0			2000.0
96+00.0		64.0	4.0	32.0
96+00.0 - 101+00.0	2000.0			2000.0
101+00.0		64.0	4.0	32.0
101+00.0 - 103+10.0	840.0			840.0
I-72 SUBTOTAL:	28,240.0	1,056.0	66.0	28,752.0
OLD 36 SUBTOTAL:	0.0	0.0	0.0	0.0
GRAND TOTAL:	28,240.0	1,056.0	66.0	28,752.0

BUTT JOINT / TEMPORARY RAMP

LOCATION	WIDTH	LENGTH	BIT SURF REMOVAL - BUTT JT	PCC SURF REMOVAL - BUTT JT	BUTT JOINT THICK.	WIDTH OF RAMP	LENGTH OF RAMP	TEMPORARY RAMP
STATION	( FT )	( FT )	( SQ YD )	( SQ YD )	( INCH )	( FT )	( FT )	( SQ YD )
I-72 EASTBOUND								
0+35.0	24.0	30.0		80.0	1.50	24.0	5.0	13.3
0+65.0	24.0	45.0		120.0	2.25	24.0	7.5	20.0
102+98.0	24.0	45.0		120.0	2.25	24.0	7.5	20.0
103+28.0	24.0	30.0		80.0	1.50	24.0	5.0	13.3
I-72 WESTBOUND								
103+58.0	24.0	30.0		80.0	1.50	24.0	5.0	13.3
102+98.0	24.0	45.0		120.0	2.25	24.0	7.5	20.0
0+65.0	24.0	45.0		120.0	2.25	24.0	7.5	20.0
0+35.0	24.0	30.0		80.0	1.50	24.0	5.0	13.3
OLD US 36								
344+50.0	24.0	50.0	133.3		2.50	24.0	8.3	22.2
366+36.5	14.0	50.0	77.8		2.50	24.0	8.3	22.2
366+36.5	14.0	50.0	77.8		2.50	24.0	8.3	22.2
368+95.5	14.0	50.0	77.8		2.50	24.0	8.3	22.2
368+95.5	14.0	50.0	77.8		2.50	24.0	8.3	22.2
385+96.0	24.0	50.0	133.3		2.50	24.0	8.3	22.2
NORTH FRONTAGE RD	VARIES	15.0	309.5*		1.50	20.0	5.0	11.1
SOUTH FRONTAGE RD	VARIES	15.0	476.2*		1.50	26.0	5.0	14.4
I-72 SUBTOTAL:			0.0	800.0				133.3
OLD 36 SUBTOTAL:			1,363.5	0.0				158.9
GRAND TOTAL:			1,363.5	800.0				292.3

\* AREA CALCULATED USING CADD

PLOT DATE = \$DATE\$  
 FILE NAME = \$FILEL\$  
 PLOT SCALE = \$SCALE\$  
 REFERENCE = \$REF\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAP 72  
 SECTION (86-10IRS-2  
 SCOTT COUNTY

SCALE: VERT.  
 HORIZ.  
 DATE

DRAWN BY  
 CHECKED BY