

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	8(L),TS,1-1)	SANGAMON	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES - IL RTE. 29 @ HILLTOP ROAD

PAY CODE	PAY ITEM DESCRIPTION	UNIT	100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				1000 RESURFACING QUANTITY	Y031-1F SIGNALS QUANTITY	Y030-1E LIGHTING QUANTITY
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1		1	
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3.5		3.5	
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1/C, (GREEN)	FOOT	1341		1341	
X8170245	ELECTRIC CABLE IN CONDUIT, 600 V (XLP - TYPE USE), 3-1/C, * 12	FOOT	524		524	
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TONS	755	755		
X8801100	SIGNAL HEAD, POLYCARBONATE, LED 1-FACE, 1-SECTION, POST MOUNTED	EACH	4		4	
X8801437	SIGNAL HEAD, POLYCARBONATE, LED 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1	
31101000	SUB BASE GRANULAR MATERIAL, TYPE B	TONS	18	18		
40600200	BITUMINOUS MATERIAL (PRIME COAT)	TONS	3.6	3.6		
40600300	AGGREGATE PRIME COAT	TONS	18	18		
* 40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	636	636		
40600990	TEMPORARY RAMPS	SQ YD	108	108		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	6104	6104		
44000100	PAVEMENT REMOVAL	SQ YD	35	35		

PLOT DATE: 2/1/2006
 FILE NAME: C:\p10\m15\050606\1\1\1000.dwg
 USER NAME: D:\p10\m15\050606\1\1\1000.dwg

Rev.

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IL 29 @ HILLTOP ROAD
 SANGAMON COUNTY

SCALE: VERT. DATE
 HORIZ. DATE

DRAWN BY
 CHECKED BY