

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	8(L,TS,I-I)	SANGAMON	29	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES - IL RTE. 29 @ HILLTOP ROAD

PAY CODE	PAY ITEM DESCRIPTION	UNIT	100% STATE	CONSTRUCTION TYPE CODE		
			TOTAL QUANTITY	1000 RESURFACING QUANTITY	Y031-1F SIGNALS QUANTITY	Y030-1E LIGHTING QUANTITY
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	4156	4156		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	201	201		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	54	54		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	113	113		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	111.1	111		
72000100	SIGN PANEL, TYPE I	SQ FT	10		10	
72000200	SIGN PANEL, TYPE II	SQ FT	22		22	
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	93.6	94		
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	4156	4156		
78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	201	201		
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	54	54		
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	113	113		
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	31	31		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	31	31		

PLOT DATE = 2/1/2006
 FILE NAME = c:\pwork\11050606\11050606.dwg
 USER NAME = b...
 USER NAME = b...

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IL 29 @ HILLTOP ROAD
 SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____