

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	BIL. TS. 1-1	SANGAMON	29	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SHORT-TERM PAVEMENT MARKING		
LOCATION	STATION	TOTAL (FOOT)
SBL	86+13.47 - 93+62.29 RT	150
NBL	91+48.64 - 98+60.67 LT	142
HILLTOP ROAD	47+45.22 - 49+50.99	41
<i>TOTAL</i>		<i>333</i>

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B			
LOCATION	STATION	LETTERS AND SYMBOLS	
		LEFT ARROW (SQ FT)	RIGHT ARROW (SQ FT)
NBL - LEFT T.L.	93+25	15.6	
NBL - LEFT T.L.	94+26	15.6	
NBL - LEFT T.L.	95+40	15.6	
SBL - RIGHT T.L.	89+14		15.6
SBL - RIGHT T.L.	90+25		15.6
SBL - RIGHT T.L.	91+44		15.6
<i>TOTAL</i>		<i>46.8</i>	<i>46.8</i>

SHORT-TERM PAVEMENT MARKING REMOVAL		
LOCATION	STATION	TOTAL (SQ FT)
SBL	86+13.47 - 93+62.29 RT	49.9
NBL	91+48.64 - 98+60.67 LT	47.5
HILLTOP ROAD	47+45.22 - 49+50.99	13.7
<i>TOTAL</i>		<i>111.1</i>

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B		
LOCATION	STATION	LINE 12" WHITE (FOOT)
		SBL / HILLTOP RD
<i>TOTAL</i>		<i>54</i>

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B		
LOCATION	STATION	LINE 24" WHITE (FOOT)
SBL - RIGHT T.L.	92+00 RT	18
SBL	92+00 RT	24
NBL / NBL LEFT T.L.	93+30 LT	38
HILLTOP ROAD	48+18 RT	33
<i>TOTAL</i>		<i>113</i>

TEMPORARY PAVEMENT MARKINGS		
ITEM	LOCATION	TOTAL
TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	(USE PERMANENT MARKING LOCATIONS)	93.6 SQ FT
TEMPORARY PAVEMENT MARKING - LINE 5"	(USE PERMANENT MARKING LOCATIONS)	4156
TEMPORARY PAVEMENT MARKING - LINE 8"	(USE PERMANENT MARKING LOCATIONS)	201
TEMPORARY PAVEMENT MARKING - LINE 12"	(USE PERMANENT MARKING LOCATIONS)	54
TEMPORARY PAVEMENT MARKING - LINE 24"	(USE PERMANENT MARKING LOCATIONS)	113

PLOT DATE: 12/19/2006
 FILE NAME: c:\purogen\14806060\hillsch.dgn
 PLOT SCALE: 1/8"=1'-0" / in.
 USER NAME: brenham

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 IL 29 @ HILLTOP ROAD
 SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY: ...
 CHECKED BY: ...