



STATION TO STATION	SAND FILL		CONCRETE MEDIAN SB (MODIFIED)		REMARKS
	CJ YD	SQ FT	SQ FT	SQ FT	
148+85.00 - 151+35.00			1500.0		RAMPED NOSE
151+35.00 - 153+61.00	40			2278.8	
153+61.00 - 159+94.00	105			5882.4	
159+94.00 - 162+54.00	63			3521.8	RAMPED NOSE
SUBTOTALS	208*	1500	11683		

OTHER QUANTITIES, SUCH AS CURB, GRANULAR MATERIAL, AND TEMPORARY PAVEMENT TABULATED ELSEWHERE

- (10) PROPOSED COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
 - (11) PROPOSED CONCRETE MEDIAN SURFACE, 4 INCH
 - (13) PROPOSED SUBBASE GRANULAR MATERIAL, TYPE C
 - (21) PROPOSED CONCRETE CURB, TYPE B (DOWELLED)
 - (22) PROPOSED SAND FILL *
 - (23) PROPOSED BIT. CONC. BINDER CRSE, SUPERPAVE, IL-19.0, N90-12"
 - (24) PROPOSED CONCRETE MEDIAN, TYPE SB (MODIFIED)
- * SAND INCLUDED IN COST OF CONCRETE MEDIAN SURFACE, 4 INCH



REVISIONS	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 INTERSECTION DETAIL
 MEDIAN LAYOUT
 STA 148+50 TO STA 163+00
 F.A.P. 103 (IL. RTE. 13/15)
 SECTION 27-1R - ST. CLAIR CO.
 SCALE: 1" = 30'
 DATE: February 11, 2005
 DRAWN BY: KEB
 CHECKED BY: RCY