F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1R	ST. CLAIR	382	176
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76300

SIGN SCHEDULE CONTINUED

SIGN	STATION	ALIGNMENT	OFFSET	SIDE	DESIGNATION	DESC.	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	OBJECT MARKER TYPE 1 EACH	WOOD POST FOOT	METAL POST TYPE B FOOT	REMARKS
87	100+00.00	AR L2	6	LT	W1-7-4824	<-->	8				29	2 @ 14.5'
88	232+40.00	FAP103	124	LT	W14-2-30	NO OUTLET	6.25			17		
89	233+13.00	FAP103	66.5	LT	R5-1-36	DO NOT ENT.	9			16.25		
90	233+13.00	FAP103	1.5	LT	R5-1-36	DO NOT ENT.	9			16.25		
91	238+09.50	FAP103	12	LT	R3-I100-24	LT TURN LN	4				13.75	
92	248+13.50	FAP103	1.5	RT	R5-1a-3624	WRONG WAY	6			15.25		
93	248+13.50	FAP103	66.5	RT	R5-1a-3624	WRONG WAY	6			15.25		
94	251+38.50	FAP103	12	RT	R4-7-2430	KEEP RT	5			15.5		
95	252+30.75	FAP103	12	RT	R4-7-2430	KEEP RT	5			15.5		
96	105+00.00	AR R3	17	RT	W14-1-30	DEAD END	6.25			17		
97	261+00.00	FAP103	66.5	RT	R2-1-3648	SP LIM 55		12		17.25		
98a	116+57.00	AR L2	NA	NA	OM4-1-18	END MARKER			1		10.5	
98b	116+57.00	AR L2	NA	NA	R11-I100-4830	RD ENDS		10			21	2 @ 10.5'
98c	116+57.00	AR L2	NA	NA	OM4-1-18	END MARKER			1		10.5	
99	249+50.00	FAP103	66.5	LT	R2-1-3648	SP LIM 55		12		17.25		
100	251+13.50	FAP103	66.5	RT	R5-1-36	DO NOT ENT.	9			16.25		
101	251+13.50	FAP103	1.5	RT	R5-1-36	DO NOT ENT.	9			16.5		
102	252+00.00	FAP103	66	LT	R6-1L-3612	1-WAY-L	3			14		
103a	252+20.00	FAP103	65	RT	R1-1-30	STOP	6.25			16.5		
103b	252+20.00	FAP103	NA	RT	R6-3-2418	DIV HWY	3			NA		
104	252+78.50	FAP103	66.5	LT	R5-1-36	DO NOT ENT.	9			16.25		
105	252+78.50	FAP103	1.5	LT	R5-1-36	DO NOT ENT.	9			16.25		
106	255+78.50	FAP103	66.5	LT	R5-1a-3624	WRONG WAY	6			15.25		
107	255+78.50	FAP103	3.5	LT	R5-1a-3624	WRONG WAY	6			15.25		
108	258+05.25	FAP103	12	LT	R3-I100-24	LT TURN LN	4				13.5	
109a	099+73.00	AR L3	NA	NA	OM4-1-18	END MARKER			1		10.5	
109b	099+73.00	AR L3	NA	NA	R11-I100-4830	RD ENDS		10			21	2 @ 10.5'
109c	099+73.00	AR L3	NA	NA	OM4-1-18	END MARKER			1		10.5	
110	094+50.00	AR L3	17	LT	W8-3-30	PMT ENDS	6.25			18.25		
111	270+88.75	FAP103	12	RT	R3-I100-24	LT TURN LN	4				13.75	
112	273+00.00	FAP103	2.5	RT	R5-1a-3624	WRONG WAY	6			15.25		
113	273+00.00	FAP103	66.5	RT	R5-1a-3624	WRONG WAY	6			15.25		
114	274+40.00	FAP103	66.5	LT	R2-1-3648	SP LIM 55		12		17.25		
115	276+00.00	FAP103	1.5	RT	R5-1-36	DO NOT ENT.	9			16		
116	276+00.00	FAP103	66.5	RT	R5-1-36	DO NOT ENT.	9			16.25		
117	276+31.00	FAP103	6	LT	R4-7-2430	KEEP RT	5			15.5		
118	277+45.75	FAP103	6	RT	R4-7-2430	KEEP RT	5			15.5		
119	279+30.00	EB EOP	41	RT	R2-5a-2430	RED SPD AH	5			16.25		
120	281+89.00	EB EOP	43	RT	W6-2-48	END D HWY		16		19.25		
121	284+00.00	EB EOP	41	RT	M1-I200-24	CNTY MILE	4				13.75	
122a	276+46.50	FAP103	65	LT	R1-1-30	STOP	6.25			16.5		
122b	276+46.50	FAP103	NA	LT	R6-3-2418	DIV HWY	3			NA		
123	099+00.00	AR L3	27	LT	W14-2-30	NO OUTLET	6.25			17		
124	277+91.50	WB EOP	41.5	LT	R5-1-36	DO NOT ENT.	9			16.25		
125	277+91.50	WB EOP	23.5	RT	R5-1-36	DO NOT ENT.	9			15.75		
126	280+91.50	WB EOP	41.5	LT	R5-1a-3624	WRONG WAY	6			15.25		
127	280+91.50	WB EOP	20.1	RT	R5-1a-3624	WRONG WAY	6			14.75		
128	282+89.50	WB EOP	13	RT	R3-I100-24	LT TURN LN	4			14.5		
129a	284+00.00	WB EOP	41.5	LT	R2-1-3648	SP LIM 55		12		18.25		
129b	284+00.00	WB EOP	NA	LT	M1-I200-24	CNTY MILE	4					
130a	290+50.00	EB EOP	42.25	RT	W2-2-36	T INTER.	9			18.75		
130b	290+50.00	EB EOP	NA	RT	W16-8-3615	TEXT	3.75					
TOTAL (RURAL)							902	208	15	1961	555	

SIGN	STATION	ALIGNMENT	OFFSET	SIDE	DESIGNATION	DESC.	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	OBJECT MARKER TYPE 1 EACH	WOOD POST FOOT	METAL POST TYPE B FOOT	REMARKS
151	294+00.00	WB EOP	43	LT	W6-1-48	BEG D HWY		16		19.25		
152a	296+00.00	WB EOP	NA	LT	M3-4-2412	WEST	2			NA		
152b	296+00.00	WB EOP	41	LT	M1-I100-2424	IL 13	4			17.25		
152c	296+00.00	WB EOP	NA	LT	M1-I100-2424	IL 15	4			NA		
153	297+37.00	WB EOP	40	LT	R1-1-30	STOP	6.25			15.5		
154	297+45.00	WB EOP	3.75	RT	R4-7-2430	KEEP RT	5				12.5	
155a	298+00.00	FAP103	53	RT	R3-9b-2436	CTR TURN	6			16.75		
155b	298+00.00	FAP103	NA	RT	R8-31218	NO PARK	1.5			NA		
156a	297+00.00	FAP103	54.25	RT	W2-2-36	T INTER.	9			19.5		
156b	297+00.00	FAP103	NA	RT	W16-8-3615	TEXT	3.75					
157a	305+00.00	FAP103	46.25	LT	W2-2-36	T INTER.	9			19.5		
157b	305+00.00	FAP103	NA	LT	W16-8-3615	TEXT	3.75			NA		
158	306+50.00	FAP103	45	LT	R2-1-2430	SP LIM 40	5			15.25		
159	305+94.00	FAP103	44	RT	R1-1-30	STOP	6.25			16		
160a	299+50.00	FAP103	44	RT	I1-I100 4830	CITY LIM		10		17.5		
160b	299+50.00	FAP103	NA	RT	R2-1-3036	SP LIM 40	7.5			NA		
161a	311+50.00	FAP103	45	RT	R3-9b-2436	CTR TURN	6			16.75		
161b	311+50.00	FAP103	NA	RT	R8-31218	NO PARK	1.5			NA		
162a	311+50.00	FAP103	45	RT	R3-9b-2436	CTR TURN	6			16.75		
162b	311+50.00	FAP103	NA	RT	R8-31218	NO PARK	1.5			NA		
163	323+63.40	FAP103	44	RT	R1-1-30	STOP	6.25			16		
164	325+00.00	FAP103	33.6	LT	R2-1-2430	SP LIM 40	5			15.25		
165	325+00.00	FAP103	45	RT	R2-1-2430	SP LIM 40	5			16.25		
166a	327+00.00	FAP103	45	RT	R3-9b-2436	CTR TURN	6			16.75		
166b	327+00.00	FAP103	NA	RT	R8-31218	NO PARK	1.5			NA		
167a	327+00.00	FAP103	33.6	LT	R3-9b-2436	CTR TURN	6			15		
167b	327+00.00	FAP103	NA	LT	R8-31218	NO PARK	1.5			NA		
168a	312+00.00	FAP103	46.25	LT	W2-2-36	T INTER.	9			19.5		
168b	312+00.00	FAP103	NA	LT	W16-8-3615	TEXT	3.75			NA		
169	332+59.50	FAP103	32.6	LT	R1-1-30	STOP	6.25			15.5		
170	336+00.00	FAP103	33.6	LT	R3-9b-2436	CTR TURN	6			14.75		
171	335+80.00	FAP103	32	RT	R1-1-30	STOP	6.25			15.5		
172	324+25.00	FAP103	45.75	RT	W9-2-30	LN ENDS	6.25			17.5		
TOTAL (URBAN)							162	26		352	25	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING AND SIGNING
SHEET 2 OF 6 SHEETS

F.A.P. 103 (IL. RTE. 13/15)
SECTION 27-1R - ST. CLAIR CO.

SCALE: NONE DRAWN BY KEB
DATE Febuary 11, 2005 CHECKED BY RCY

J:\2002\02058\DGN\CIVIL\DGN\signing_striping_03.sch-sign.dgn 3/11/2005 8:37:28 AM