

EARTHWORK SCHEDULE (IL 3)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 620+00 TO STA. 620+50	1.4	1.1	0.0	1.1
STA 620+50 TO STA. 621+00	3.0	2.3	0.2	2.1
STA 621+00 TO STA. 621+50	4.1	3.1	0.8	2.3
STA 621+50 TO STA. 622+00	5.3	4.0	4.3	-0.3
STA 622+00 TO STA. 622+50	5.3	4.0	17.5	-13.5
STA 622+50 TO STA. 623+00	4.4	3.3	68.4	-65.1
STA 623+00 TO STA. 623+50	3.7	2.8	74.3	-71.5
STA 623+50 TO STA. 624+00	3.5	2.6	37.4	-34.8
STA 624+00 TO STA. 624+50	3.4	2.6	69.8	-67.3
STA 624+50 TO STA. 625+00	3.3	2.5	88.6	-86.1
STA 625+00 TO STA. 625+50	5.5	4.1	51.4	-47.3
STA 625+50 TO STA. 626+00	7.7	5.8	26.1	-20.3
STA 626+00 TO STA. 626+50	8.8	6.6	16.7	-10.1
STA 626+50 TO STA. 627+00	10.5	7.9	8.6	-0.7
STA 627+00 TO STA. 627+50	12.2	9.2	6.7	2.5
STA 627+50 TO STA. 628+00	13.2	9.9	5.3	4.6
STA 628+00 TO STA. 628+50	12.6	9.5	4.7	4.8
STA 628+50 TO STA. 629+00	12.4	9.3	7.2	2.1
STA 629+00 TO STA. 629+50	13.1	9.8	8.3	1.5
STA 629+50 TO STA. 630+00	12.9	9.7	9.4	0.3
STA 630+00 TO STA. 630+50	11.6	8.7	10.2	-1.5
STA 630+50 TO STA. 631+00	11.0	8.3	8.2	0.1
STA 631+00 TO STA. 631+50	10.8	8.1	6.3	1.8
STA 631+50 TO STA. 632+00	10.1	7.6	5.7	1.9
STA 632+00 TO STA. 632+50	8.6	6.5	7.3	-0.9
STA 632+50 TO STA. 633+00	3.8	2.9	4.4	-1.6
TOTAL	202.2	151.7	547.8	-396.2

SIGN SCHEDULE

EXISTING LOCATION	EXISTING OFFSET FROM EX EOP (FT)	PROPOSED LOCATION (APPROX.)	PROPOSED OFFSET FROM NEW EOP (APPROX. - FT)	RELOCATE SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 1 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH)	RELOCATE EXISTING SIGNS (EACH)	DESCRIPTION
N. MAIN ST.		114+16	18' RT		4	16				NEW R3-1100R 24"X24" "RIGHT TURN LANE"
AT DALEVIEW DR.										
114+31	11' RT								1	EXISTING "STOP"
114+29	8' RT								1	EXISTING "N.MAIN/DALEVIEW"
		ISLAND			9		10	1		NEW W12-1 36"
		MAST ARM ASSEMBLY AND POLE		12.5	5					2 EXISTING SIGN PANELS NEW "RIGHT TURN AT ALL TIMES"
NB IL 3										
		635+00	19' RT		9	18				NEW W4-3R 36"
631+50	13' RT	SAME	19' RT						1	EXISTING "IL 3"
629+80	17' RT	SAME	20' RT						1	EXISTING SIGN ON 2 POSTS
628+32	15' RT	SAME	19' RT						1	EXISTING SIGN ON 1 POST
627+29	15' RT	SAME	19' RT						1	EXISTING SIGN ON 1 POST
TOTALS				12.5	27	34	10	1	6	

EARTHWORK SCHEDULE (NORTH MAIN ST.)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 112+50 TO STA. 113+00	2.9	2.2	0.4	1.8
STA 113+00 TO STA. 113+50	4.5	3.4	0.5	2.9
STA 113+50 TO STA. 114+00	4.5	3.4	2.3	1.1
STA 114+00 TO STA. 115+00	20.3	15.2	6.2	9.0
STA 115+00 TO STA. 115+50	12.9	9.7	0.9	8.8
STA 115+50 TO STA. 116+00	6.7	5.0	0.0	5.0
STA 116+00 TO STA. 116+50	1.1	0.8	0.0	0.8
TOTAL	52.9	39.7	10.3	29.4

DRAINAGE SCHEDULE

LOCATION	SIDE	PIPE CULVERT REMOVAL (FT)	PIPE UNDERDRAINS 4" (FT)	PIPE UNDERDRAINS 4" (SPECIAL) (FT)	CONCRETE HEAD-WALL FOR PIPE UNDERDRAINS (EACH)
DALEVIEW DRIVE		65			
NORTHBOUND IL 3					
STA. 632+35 TO 627+00 RT			535		
STA. 627+00 RT				7	1
STA. 627+00 TO 622+00 RT			500		
STA. 622+00 RT				7	1
STA. 622+00 TO 620+12 RT			188		
TOTALS		65	65	1223	14

*FURNISHED EXCAVATION (CU YD) = 396.2 - 29.4 = 367 CU YD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
 FAP ROUTE 312 (IL 3)
 SECTION 66-31
 MONROE COUNTY
 SCALE: VERT. _____ HORIZ. _____
 DATE _____ DRAWN BY _____ CHECKED BY _____

PLOT DATE = 2/6/2006
 FILE NAME = c:\pcc\projects\11487308\plan\11487308.dgn
 PLOT SCALE = 3/8" = 1' IN.
 REFERENCE = REF#