

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
312	66-31	MONROE	45	22
STA.		TO STA.		
CONTRACT NO. 16992				

SCHEDULE OF QUANTITIES			CONSTRUCTION TYPE CODE Y031-IF		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	-----	-----
72000100	SIGN PANEL - TYPE 1	SQ FT	5	5	
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	12.5	12.5	
80300100	LOCATING UNDERGROUND CABLE	FOOT	500	500	
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	13.5	13.5	
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	140	140	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	15.5	15.5	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	169	169	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	472.5	472.5	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	278.5	278.5	
87700320	STEEL MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1	1	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	20	20	
88600100	DETECTOR LOOP, TYPE I	FOOT	224	224	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	684	684	
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	2049.5	2049.5	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1	
X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	
X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1	1	
X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1	1	
X8950200	REBUILD EXISTING HANDHOLE	EACH	2	2	
X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	1	1	

ILLINOIS DEPARTMENT OF TRANSPORTATION
TRAFFIC SIGNAL
SCHEDULE OF QUANTITIES

FAP ROUTE 312
SECTION 66-31
MONROE COUNTY