

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	125-R	MADISON	47	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

1000-1A

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE J000-2A		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FEDERAL 10% STATE URBAN	
20200100	EARTH EXCAVATION	CU YD	4580	4580	
25000200	SEEDING, CLASS 2	ACRE	2	2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	61	61	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	61	61	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	61	61	
25100115	MULCH, METHOD 2	ACRE	2	2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	78	78	
28000300	TEMPORARY DITCH CHECKS	EACH	58	58	
28000500	INLET AND PIPE PROTECTION	EACH	11	11	
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	7163	7163	
30201500	LIME	TON	138	138	
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	480	480	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	694	694	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6	
40600300	AGGREGATE (PRIME COAT)	TON	23	23	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	40	40	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	89	89	
40600990	TEMPORARY RAMP	SQ YD	54	54	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	81	81	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	117	117	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	6321	6321	
44000100	PAVEMENT REMOVAL	SQ YD	1184	1184	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	427	427	
44000400	GUTTER REMOVAL	FOOT	242	242	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1902	1902	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6928	6928	
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	1361	1361	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	1788	1788	
50105220	PIPE CULVERT REMOVAL	FOOT	407	407	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	22	22	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3	
54248510	CONCRETE COLLAR	CU YD	1.5	1.5	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	467	467	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	23	23	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE J000-2A		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FEDERAL 10% STATE URBAN	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4.4	4.4	
60602500	CONCRETE GUTTER, TYPE A	FOOT	515	515	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1212	1212	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	468	468	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16710	16710	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	203	203	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	109	109	
72000100	SIGN PANEL - TYPE 1	SQ FT	85	85	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10	
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2	
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1	
73000100	WOOD SIGN SUPPORT	FOOT	197	197	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	468	468	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16710	16710	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	203	203	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	199	199	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	45	45	
X3550715	BITUMINOUS BASE COURSE SUPERPAVE 10 3/4"	SQ YD	4897	4897	
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	1211	1211	
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	752	752	

\* SPECIALTY ITEMS

PLOT DATE = 2/22/2005  
 FILE NAME = \\s019985\plm\p1049985.dgn  
 PLOT SCALE = 43.5000 / IN.  
 REFERENCE = REF6