ORIGINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
NOTE BOOK	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

FINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
NOTE BOOK	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

SEGMENT 1 STAGE 1 SEGMENT 1 STAGE 2

CROSSROAD

13+19.38

EXIST. R.O.W. 711.55 711.92 712.21 0.4%

13+00.00

EXIST. R.O.W. 711.28 711.51 711.82 711.45 EXIST. R.O.W.

EARTH EXCAVATION 6.5 SQ FT
EMBANKMENT 1.0 SQ FT
UNSUITABLE 2.1 SQ FT

EARTH EXCAVATION 7.8 SQ FT
EMBANKMENT 0.5 SQ FT
UNSUITABLE 1.2 SQ FT

12+50.00

EXIST. R.O.W. 710.22 710.46 710.76 710.53 EXIST. R.O.W.

EARTH EXCAVATION 4.5 SQ FT
EMBANKMENT 1.0 SQ FT
UNSUITABLE 1.4 SQ FT

EARTH EXCAVATION 4.7 SQ FT
EMBANKMENT 0.6 SQ FT
UNSUITABLE 0.8 SQ FT

12+37.00

EXIST. R.O.W. 709.94 710.29 710.52 710.21 EXIST. R.O.W.

EARTH EXCAVATION 7.2 SQ FT
EMBANKMENT 1.2 SQ FT
UNSUITABLE 1.5 SQ FT

EARTH EXCAVATION 7.1 SQ FT
EMBANKMENT 0.9 SQ FT
UNSUITABLE 0.9 SQ FT

12+21.09

709.92 710.23 2% EXIST. R.O.W.

SEGMENT 1 STAGE 1 SEGMENT 1 STAGE 2

CROSSROAD

12+00.00

1.6% 709.57 709.87 2% 2% EXIST. R.O.W.

11+50.00

EXIST. R.O.W. 708.93 709.14 2% 2% EXIST. R.O.W.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0306	01-00029-00-FP	WILL	118	96
FED. ROAD DIST. NO. -	ILLINOIS FED. AID PROJECT			
STA.	TO STA.			

CONTRACT NO. 83825