


- NOTES: ONCE PREEMPTION HAS BEEN CALLED, TERMINATION OF A PHASE(S) SHLL BE IDENTICAL TO THE NORMAL SEQUENCE OF OPERATION'S TERMINATION OF A PHASE(S) AS DESCRIBED IN STANDARD 2393.
- 2. CONTINUATION OR TERMINATION OF ALL RIGHT TURN OVERLAP'S SHALL BE IDENTICAL TO THE NORMAL SEQUENCE OF OPERATIONS CONTINUATION OR TERMINATION OF RIGHT TURN OVERLAP'S AS DESCRIBED IN THE CLEARANCE NOTES FOR RIGHT TURN OVERLAP'S.
- 3. TERMINATION OF ALL PEDESTRIAN PHASES SHALL INCLUDE A FULL FLASHING "DON'T WALK" INTERVAL.
- 4. IF ALL RED CLEARANCE IS USED IN THE NORMAL SEQUENCE OF OPERATION, IT MUST BE DISPLAYED AFTER THE YELLOW CLEARANCE INTERVAL WHEN ENTERING OR LEAVING THE PREEMPTION SEQUENCE.



ALGONQUIN	RD	SIDEWALK	IMPRO	V	ΈN	1EN	TS
SCALE		FILE NAME		SI	HEE	f NO.	
NTS		CABLE.DWG		1	1	OF	2

CABLE PLAN

STA.	TO STA.			
ROUTE NUMBER	SECTION NUMBER	COUNTY		
339	02-00073-00-SW	COOK		
CONTRACT	NO 97976	·		

CABLE PLAN LEGEND

EXISTING PROPOSED

R (3)

 \square

0

(2)

12" TRAFFIC SIGNAL SECTION 12" PEDESTRIAN SIGNAL SECTION

CONTROLLER CABINET SERVICE INSTALLATION

VEHICLE DETECTOR, INDUCTION LOOP

PUSHBUTTON DETECTOR

DENOTES NUMBER OF CONDUCTORS ALL LOOP DETECTOR CABLE TO BE SHIELDED. ALL CABLE NO. 14 EXCEPT

 $\triangleright \infty$ EMERGENCY VEHICLE SYSTEM DETECTOR CONFIRMATION BEACON

Dod

SIGNAL FACE WITH BACKPLATE "P" INDICATES PROGRAMMED HEAD.

PEDESTRIAN PUSH BUTTON NOTES Pedestrian Pushbutton "D" shall place a

SCHEDULE OF QUANTITES

CABLE PLAN

QUANTITY	UNIT	PAY ITEM
25	FT	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL
1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
405	FT	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 2/C
405	FT	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 3/C
2	EACH	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT
8	FT	CONCRETE FOUNDATION, TYPE A
2	EACH	DRILL EXISTING HANDHOLE
2	EACH	PEDESTRIAN PUSH BUTTON
1	EACH	MODIFY EXISTING CONTROLLER
6	EACH	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED

ILLINOIS DEPARTMENT OF TRANSPORTATION

CABLE PLAN

SCALE: NTS DRAWN BY: SW DATE: 9/29/05

CHECKED BY: SW