

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S.B.:	04-00137-03-FP	HENRY	31	2
F.A.:	224			
FED. ROAD DIST. NO. 7		ILL. INDIC.	FED. AID PROJECT OR-0041507	

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 1000-2A

CODE NO.	ITEM	UNIT	TOTAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	40
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	192
* 20200410	EARTH EXCAVATION (SPECIAL)	CU YD	3,782
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100
20800150	TRENCH BACKFILL	CU YD	22
21301052	EXPLORATION TRENCH, 52" DEPTH	FOOT	310
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	140
25000500	PHOSPHUROUS FERTILIZER NUTRIENT	POUND	140
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	140
25000200	SEEDING, CLASS 2	ACRE	1.55
25100115	MULCH METHOD 2	ACRE	1.55
25100630	EROSION CONTROL BLANKET	SQ YD	462
28000300	TEMPORARY DITCH CHECK	EACH	14
28000400	PERIMETER EROSION BARRIER	FOOT	600
* 31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TONS	1,600
* 35100100	AGGREGATE BASE COURSE, TYPE A	TONS	1,050
* 40200800	AGGREGATE SURFACE COURSE, TYPE B	TONS	30
* 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,863
* 40600300	AGGREGATE (PRIME COAT)	TONS	14
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	201
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY, 7"	SQ YD	8
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,224
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	1,465
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	1
* 542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	114
* 542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	6
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	88
* 60101905	PIPE DRAINS, 10" SPECIAL	FOOT	319
* 60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	367
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	16
67100100	MOBILIZATION	L SUM	1
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	408
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	204
72000100	SIGN PANEL TYPE 1	SQ FT	6.25
72900100	METAL POST - TYPE A	FOOT	12
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,531
Δ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	783
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	463
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	23
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	122
X3550010	BITUMINOUS BASE COURSE SUPERPAVE	TONS	918
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TONS	1,087
* Z0005400	BREAKER-RUN CRUSHED STONE	TON	205
* XX005728	INLETS WITH SPECIAL FRAME AND GRATE	EACH	1

Δ SPECIALTY ITEMS