

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
224	04-00137-03-FP	HENRY	31	8
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT 3R-24071	

SCHEDULES

CON'T.

THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS		
STATION	SQ FT	REMARKS
683+21	15.6	LEFT TURN ARROW
684+04	15.6	LEFT TURN ARROW
685+69	15.6	LEFT TURN ARROW
686+49	15.6	LEFT TURN ARROW
687+24	15.6	LEFT TURN ARROW
688+02	15.6	LEFT TURN ARROW
LT 689+56	15.6	RIGHT TURN ARROW
LT 690+30	15.6	RIGHT TURN ARROW
LT 691+05	15.6	RIGHT TURN ARROW
LT 691+89	15.6	RIGHT TURN ARROW
PROJECT TOTAL	156	

78000100

THERMOPLASTIC PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
Wolf Rd.		
LT 678+10.84 - 687+38.21	928	WHITE EDGE LINE
RT 689+34.01 - 698+64.17	930	WHITE EDGE LINE
RT 678+10.84 - 698+64.17	2,053	WHITE EDGE LINE
LT & RT 678+85.84 - 682+38	1,348	DBL YELLOW-CL & MEDIAN
LT & RT 682+99.27 - 688+24.27	1,052	DBL YELLOW-CL & MEDIAN
LT & RT 689+10 - 697+89.01	3,450	DBL YELLOW-CL & MEDIAN
Intersection		
NW Radius	145	WHITE EDGE LINE
NE Radius	148	WHITE EDGE LINE
1280 East Rd.		
LT 40+84 - 42+03	119	WHITE EDGE LINE
RT 41+53 - 42+03	50	WHITE EDGE LINE
40+49 - 42+03	308	DBL YELLOW-CL
PROJECT TOTAL	10,531	

78000200

THERMOPLASTIC PAVEMENT MARKING - LINE 8"		
STATION	FOOT	REMARKS
LT 682+99.27 - 684+14.20	115	WHITE TURN LANE
LT 684+14.20 - 685+59.27	36	WHITE 3-9 SKIP DASH
RT 684+14.20 - 685+59.27	36	WHITE 3-9 SKIP DASH
RT 685+59.27 - 688+24.27	265	WHITE TURN LANE
RT 689+34.01 - 691+99.01	265	WHITE TURN LANE
RT 691+99.01 - 694+64.01	66	WHITE 3-9 SKIP DASH
PROJECT TOTAL	783	

78000500

INLET SPECIAL WITH FRAME AND GRATE		
STATION	EACH	REMARKS
RT. 682+95	1	
PROJECT TOTAL	1	

THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
STATION	FOOT	REMARKS
LT & RT 678+85.84 - 682+38	85	YELLOW MEDIAN MARKING
LT & RT 689+10 - 697+89.01	378	YELLOW MEDIAN MARKING
PROJECT TOTAL	463	

78000600

THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
LT 40+49	23	STOP LINE
PROJECT TOTAL	23	

78000650

BREAKER-RUN CRUSHED STONE		
STATION	TONS	REMARKS
CONTINGENCY ITEM	205	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	205	

Z0005400

RAISED REFLECTIVE PAVEMENT MARKER		
STATION	EACH	REMARKS
Wolf Rd.		
677+78	1	2-WAY AMBER MARKER
678+18	1	2-WAY AMBER MARKERS
678+58	1	2-WAY AMBER MARKERS
678+86	1	1-WAY AMBER MARKERS
LT & RT 679+38	2	1-WAY AMBER MARKERS
LT & RT 679+78	2	1-WAY AMBER MARKERS
LT & RT 680+18	2	1-WAY AMBER MARKERS
LT & RT 680+58	2	1-WAY AMBER MARKERS
LT & RT 680+98	2	1-WAY AMBER MARKERS
LT & RT 681+38	2	1-WAY AMBER MARKERS
LT & RT 681+78	2	1-WAY AMBER MARKERS
LT & RT 682+18	2	1-WAY AMBER MARKERS
LT 682+29	1	1-WAY AMBER MARKER
RT 682+38	2	1-WAY AMBER MARKERS
LT 683+00	1	1-WAY CRYSTAL MARKER
RT 683+00	2	2-WAY AMBER MARKERS
LT 683+44	1	1-WAY CRYSTAL MARKER
RT 683+44	2	2-WAY AMBER MARKERS

CON'T.

LT 683+84	1	1-WAY CRYSTAL MARKER
RT 683+84	2	2-WAY AMBER MARKERS
LT 684+14	1	1-WAY CRYSTAL MARKER
RT 684+24	2	2-WAY AMBER MARKERS
RT 684+64	2	2-WAY AMBER MARKERS
LT 685+04	2	2-WAY AMBER MARKERS
LT 685+44	2	2-WAY AMBER MARKERS
RT 685+60	1	1-WAY CRYSTAL MARKER
LT 685+84	2	2-WAY AMBER MARKERS
RT 685+84	1	1-WAY CRYSTAL MARKER
LT 686-24	2	2-WAY AMBER MARKERS
RT 686+24	1	1-WAY CRYSTAL MARKER
LT 686+64	2	2-WAY AMBER MARKERS
RT 686+64	1	1-WAY CRYSTAL MARKER
LT 687+04	2	2-WAY AMBER MARKERS
RT 687+04	1	1-WAY CRYSTAL MARKER
LT 687+44	2	2-WAY AMBER MARKERS
RT 687+44	1	1-WAY CRYSTAL MARKER
LT 687+84	2	2-WAY AMBER MARKERS
RT 687+84	1	1-WAY CRYSTAL MARKER
LT 688+24	2	2-WAY AMBER MARKERS
RT 688+24	1	1-WAY CRYSTAL MARKER
LT 689+10	2	1-WAY AMBER MARKERS
LT 689+34	1	1-WAY CRYSTAL MARKER
LT & RT 689+50	2	1-WAY AMBER MARKERS
LT 689+74	1	1-WAY CRYSTAL MARKER
LT & RT 689+90	2	1-WAY AMBER MARKERS
LT 690+14	1	1-WAY CRYSTAL MARKER
LT & RT 690+30	2	1-WAY AMBER MARKERS
LT 690+54	1	1-WAY CRYSTAL MARKER
LT & RT 690+70	2	1-WAY AMBER MARKERS
LT 690+94	1	1-WAY CRYSTAL MARKER
LT & RT 691+10	2	1-WAY AMBER MARKERS
LT 691+34	1	1-WAY CRYSTAL MARKER
LT & RT 691+50	2	1-WAY AMBER MARKERS
LT 691+74	1	1-WAY CRYSTAL MARKER
LT & RT 691+90	2	1-WAY AMBER MARKERS
LT 691+99	1	1-WAY CRYSTAL MARKER
LT & RT 692+30	2	1-WAY AMBER MARKERS
LT & RT 692+70	2	1-WAY AMBER MARKERS
LT & RT 693-10	2	1-WAY AMBER MARKERS
LT & RT 693+50	2	1-WAY AMBER MARKERS
LT & RT 693+90	2	1-WAY AMBER MARKERS
LT & RT 694+30	2	1-WAY AMBER MARKERS
LT & RT 694+70	2	1-WAY AMBER MARKERS
LT & RT 695+10	2	1-WAY AMBER MARKERS
LT & RT 695+50	2	1-WAY AMBER MARKERS
LT & RT 695+90	2	1-WAY AMBER MARKERS
LT & RT 696-30	2	1-WAY AMBER MARKERS
LT & RT 696-70	2	1-WAY AMBER MARKERS
LT & RT 697+10	2	1-WAY AMBER MARKERS
LT & RT 697-50	2	1-WAY AMBER MARKERS
LT & RT 697+89	2	1-WAY AMBER MARKERS
698+30	1	2-WAY AMBER MARKER
698+70	1	2-WAY AMBER MARKER
699+10	1	2-WAY AMBER MARKER
1280 East Rd.		
40+49	1	2-WAY AMBER MARKERS
41+29	1	2-WAY AMBER MARKERS
PROJECT TOTAL	122	

78100100