

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: I000

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
89	04-00229-00-FP	OGLE	42	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

	CODE	ITEM	UNIT	TOTAL	
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	66	
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	324	
3	20200410	EARTH EXCAVATION (SPECIAL)	CU YD	13,010	
4	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	
5	25000350	SEEDING, CLASS 7	ACRE	7.08	
6	25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	1.28	
7	25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	5.80	
8	25100630	EROSION CONTROL BLANKET	SQ YD	1,066	
9	28000300	TEMPORARY DITCH CHECKS	EACH	30	
10	28000400	PERIMETER EROSION BARRIER	FOOT	500	
11	28000500	INLET AND PIPE PROTECTION	EACH	4	
12	31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	16,064	
13	35100100	AGGREGATE BASE COURSE, TYPE A	TON	5,877	
14	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30	
15	40500300	BITUMINOUS MIXTURE COMPLETE	TON	208	
16	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13,632	
17	40600300	AGGREGATE (PRIME COAT)	TON	34	
18	48100100	AGGREGATE SHOULDERS, TYPE A	TON	3,521	
19	48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	248	
20	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	6	
21	542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	179	
22	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	796	
23	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	
24	60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	161	
25	60602900	CONCRETE GUTTER, TYPE B (MODIFIED)	FOOT	203	
26	60603300	GUTTER OUTLET	FOOT	16	
27	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	21	
28	66600400	REMOVE AND RE-ERECT RIGHT OF WAY MARKERS	EACH	1	
29	67100100	MOBILIZATION	L SUM	1	
30	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	
31	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	728	
32	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	243	
*	33	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,930
*	34	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48
	35	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1,958
	36	XX005347	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, N50	TON	1,958
	37	Z0005400	BREAKER-RUN CRUSHED STONE	TON	205

*SPECIALTY ITEMS