



- 1 PAVEMENT REMOVAL
LT. & RT. STA. 16+75.00 TO STA. 17+25.00
- 2 SIDEWALK REMOVAL
RT. STA. 16+11.73 TO STA. 16+83.20
RT. STA. 17+12.62 TO STA. 17+84.96
RT. STA. 17+95.28 TO STA. 18+61.80
RT. STA. 18+74.13 TO STA. 18+86.02
RT. STA. 19+05.62 TO STA. 19+73.94
RT. STA. 19+88.41 TO STA. 20+50.78
RT. STA. 20+92.80 TO STA. 22+00.00
- 3 DRIVEWAY PAVEMENT REMOVAL
LT. STA. 17+09
LT. STA. 17+74
RT. STA. 17+90
LT. STA. 18+44
RT. STA. 18+68
RT. STA. 18+95
LT. STA. 19+25
RT. STA. 19+82
LT. STA. 20+12
LT. STA. 20+61
LT. STA. 21+10
LT. STA. 21+66

- 6 REMOVE EXISTING MANHOLE
STA. 18+81.59, 18.01' RT.
STA. 18+82.96, 18.50' LT.
- FENCE REMOVAL
SPLIT RAIL FENCE TO BE REMOVED AND RE-ERECTED
STA. 17+15.82, 54.27' RT. TO STA. 17+84.55, 24.41' RT.
CHAIN LINK FENCE REMOVAL
STA. 19+69.07, 19.25' LT. TO STA. 19+69.11, 23.77' LT.
- 8 PIPE CULVERT REMOVAL 12"
RT. STA. 18+60.06 TO STA. 18+81.59
PIPE CULVERT REMOVAL 12"
RT. STA. 18+81.59 TO STA. 19+10.60
PIPE CULVERT REMOVAL 12"
LT. STA. 19+17.72 TO STA. 19+31.46
PIPE CULVERT REMOVAL 10"
LT. STA. 20+04.14 TO STA. 20+18.72
PIPE CULVERT REMOVAL 12"
RT. STA. 20+87.10 TO STA. 20+90.86
PIPE CULVERT REMOVAL 10"
LT. STA. 21+58.86 TO STA. 21+73.44
- 10 STORM SEWER REMOVAL, 12"
STA. 18+81.59, 18.01' RT. TO STA. 18+82.96, 18.50' LT.

LEGEND

- 1 [Hatched Box] PAVEMENT REMOVAL
- 2 [Dotted Box] SIDEWALK REMOVAL
- 3 [Diagonal Lines Box] DRIVEWAY PAVEMENT REMOVAL
- 4 [X-X-X-X Box] COMBINATION CURB AND GUTTER REMOVAL
- 6 [Circle with X] REMOVE EXISTING MANHOLE
- 8 [Circle with X] PIPE CULVERT REMOVAL
- 9 [Circle with X] RETAINING WALL REMOVAL
- 10 [Circle with X] STORM SEWER REMOVAL
- 11 [Circle with X] TREE REMOVAL
- 12 [Circle with X] REMOVE EXISTING INLET

STS CONSULTANTS
111 E. Jefferson Ave.
Peoria, Illinois 61602
PH: 309/795-8464
FAX: 309/795-5445
IL Design Firm Reg. No. 184-001518

**LAFAYETTE AVE.
BARTONVILLE IL.**

**REMOVAL PLANS
STA. 16+00 TO STA. 22+00**

SURVEY	CHECKED	ISSUE DATE
DESIGN	APPROVED	PRELIM. DATE
DRAWN	CSA	PROJECT NO. BART001

L:\BART001\DWG\REMOVAL02.DWG 1:1