



SCALES:
 1" = 20' HOR
 1" = 5' VER

LEGEND

- | | | | | |
|---|--|-------------------------------------|---|-------------------------|
| ① | | PAVEMENT REMOVAL | ⑥ | REMOVE EXISTING MANHOLE |
| ② | | SIDEWALK REMOVAL | ⑧ | PIPE CULVERT REMOVAL |
| ③ | | DRIVEWAY PAVEMENT REMOVAL | ⑨ | RETAINING WALL REMOVAL |
| ④ | | COMBINATION CURB AND GUTTER REMOVAL | ⑩ | STORM SEWER REMOVAL |
| ⑤ | | TREE REMOVAL | ⑪ | REMOVE EXISTING INLET |
| ⑫ | | | | |

- FENCE REMOVAL**
 CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED
 STA. 33+05.49, 21.99 LT. TO STA. 33+20.27, 22.16 LT.
- ② SIDEWALK REMOVAL
 LT. STA. 28+07.46 TO STA. 28+53.94
 LT. STA. 28+71.31 TO STA. 29+42.54
 LT. STA. 29+85.31 TO STA. 29+94.83
 LT. STA. 30+29.77 TO STA. 30+95.38
 LT. STA. 31+06.83 TO STA. 31+84.53
 LT. STA. 32+13.38 TO STA. 32+93.09
 LT. STA. 33+04.37 TO STA. 34+00.00
- ③ DRIVEWAY PAVEMENT REMOVAL
 LT. STA. 30+25
 RT. STA. 30+93
 LT. STA. 31+01
 RT. STA. 31+9
 RT. STA. 33+04
- ④ REMOVE EXISTING MANHOLE
 STA. 33+15.05, 20.20' RT.
 STA. 33+48.34, 13.52' LT.
- ⑧ PIPE CULVERT REMOVAL 12"
 LT. STA. 29+47.87 TO STA. 29+87.28
 PIPE CULVERT REMOVAL 12"
 LT. STA. 29+89.03 TO STA. 30+47.25
 PIPE CULVERT REMOVAL 12"
 LT. STA. 30+93.48 TO STA. 31+17.11
 PIPE CULVERT REMOVAL 12"
 LT. STA. 31+84.75 TO STA. 32+04.98
- ⑨ RETAINING WALL REMOVAL
 STA. 32+27.03, 43.82' RT. TO STA. 32+89.44, 23.99' RT.
- ⑩ STORM SEWER REMOVAL, 12"
 LT. STA. 32+37.65 TO STA. 33+48.34
 LT. STA. 33+48.34 TO RT. STA. 33+15.05
 RT. STA. 32+92.39 TO STA. 33+15.05
 LT. STA. 33+14.85 TO RT. STA. 33+15.05
- ⑪ TREE REMOVAL
 STA. 30+53.92, 19.89' RT.
 STA. 30+77.30, 21.13' RT.
 STA. 52+87.70, 34.50' RT.
 STA. 52+96.14, 38.43' RT.
- ⑫ REMOVE EXISTING INLET
 STA. 32+37.65, 14.74' LT.

STS CONSULTANTS
 111 NE Jefferson Ave.
 Peoria, Illinois 61602
 Ph: (309) 676-8484
 Fax: (309) 676-5445
 IL Design Firm Reg. No. 184-001518

**LAFAYETTE AVE.
 BARTONVILLE IL.**

**REMOVAL PLANS
 STA. 28+00 TO STA. 34+00**

SURVEY	CHECKED	ISSUE DATE
DESIGN	APPROVED	PRELIM. DATE
DRAWN		PROJECT NO.
		BART0001

SHEET
21
 OF
83