

SUMMARY OF QUANTITIES

\$USER\$
\$DATE\$
DON-SPEC

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	QUANTITIES	1000-2A	Y003	
60500060	REMOVING INLETS	EACH	25	25		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	990	990		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	14971	14971		
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	211	211		
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	800	800		
66700095	PERMANENT SURVEY MARKERS	EACH	16	16		
*66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2585	2585		
*66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
*66900530	SOIL DISPOSAL ANALYSIS	EACH	10	10		
*66901000	BACKFILL PLUGS	CU YD	145	145		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3000	3000		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	3304	3304		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43721	43721		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3033	3033		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2751	2751		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	356	356		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2000	2000		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1652	1652		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21861	21861		
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1517	1517		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1376	1376		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	178	178		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	189	189		

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	QUANTITIES	1000-2A	Y003	
*A2000716	TREE, ACER PLATANOIDES COLUMNARE, (COLUMNAR NORWAY MAPLE), 2" CALIPER BALLED AND BURLAPPED	EACH	5		5	
*A2001216	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5		5	
*A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5		5	
*A2002320	TREE, BETULA NIGRA (RIVER BIRCH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5		5	
*B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5		5	
*D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	5		5	
X0301828	ENGINEERED BARRIER	SO YD	275	275		
X0712400	TEMPORARY PAVEMENT	SO YD	627	627		
X0919000	TEMPORARY PAVEMENT REMOVAL	SO YD	627	627		
X0976600	END SECTIONS TO BE REMOVED AND REINSTALLED	EACH	1	1		
X3550900	BITUMINOUS BASE COURSE SUPERPAVE 12"	SO YD	6673	6673		
X3560160	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 12 INCH	SO YD	4347	4347		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	31	31		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	45	45		
X4023000	TEMPORARY ACCESS (ROAD)	EACH	35	35		
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	3951	3951		
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	388	388		
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	1881	1881		
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	120	120		
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0068200	STEEL CASINGS 30"	FOOT	100	100		
Z0068400	STEEL CASINGS 42"	FOOT	50	50		
Z0068412	STEEL CASINGS 54"	FOOT	50	50		
Z0076600	TRAINEES	HOURL	500	500		

* SPECIALTY ITEMS
@ Y080

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____

REVISED 12/20/05