

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9315	00-00032-00-RP	MONROE	49	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 97264				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN - MONROE COUNTY	
			FEDERAL 75% CITY 25%	TOTAL QUANTITY
				J000-2A
20200100	EARTH EXCAVATION	CU. YD.	1268	
20400800	FURNISHED EXCAVATION	CU. YD.	421	
20900110	POROUS GRANULAR BACKFILL	CU. YD.	1477	
* 20900330	GRANULAR BACKFILL	TON	81	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SG. YD.	1083	
25000110	SEEDING, CLASS 1A	ACRE	0.3	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6	
* 25101005	HEAVY DUTY EXCELSIOR BLANKET	SG. YD.	1225	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30	
28000400	PERIMETER EROSION BARRIER	FOOT	158	
28100705	STONE DUMPED RIPRAP, CLASS A3	SG. YD.	813	
28200200	FILTER FABRIC	SG. YD.	813	
31100300	SUBBASE GRANULAR MATERIAL, TYPE A, 4"	SG. YD.	2573	
31100700	SUBBASE GRANULAR MATERIAL, TYPE A, 8"	SG. YD.	225	
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SG. YD.	754	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	281	
40600300	AGGREGATE (PRIME COAT)	TON	2	
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SG. YD.	1571	
42001300	PROTECTIVE COAT	SG. YD.	2175	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SG. YD.	203	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SG. FT.	1743	
* 42400800	DETECTABLE WARNINGS	SG. FT.	150	
44000100	PAVEMENT REMOVAL	SG. YD.	252	
44000600	SIDEWALK REMOVAL	SG. FT.	85	
* 50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	
* 50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	
50300225	CONCRETE STRUCTURES	CU. YD.	27.4	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2070	
51500100	NAME PLATES	EACH	1	
54000900	BOX CULVERT END SECTIONS, SPECIAL	EACH	1	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	3	
54021006	PRECAST CONCRETE BOX CULVERT 10'x6' (M273)	FOOT	376.2	
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	54	
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	64	
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	12	
55100500	STORM SEWER REMOVAL 12"	FOOT	51	
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SG. YD.	96	
60100915	PIPE DRAINS 6"	FOOT	50	
* 60101805	PIPE DRAINS 8" (SPECIAL)	FOOT	8	
* 60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	1	
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	2	
* 60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	2	
60500060	REMOVING INLETS	EACH	1	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	744	
67100100	MOBILIZATION	L. SUM	1	
* 70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	500	
Δ 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	1488	
Δ 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	63	
* Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	360	
* Z0073500	TEMPORARY SUPPORT SYSTEM	L. SUM	1	
* X0321865	ANTI-GRAFFITI PROTECTION SYSTEM	SG. FT.	2746	
* X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	24	
* X0323410	TRIANGULAR SILT DIKES	EACH	4	
* X0330200	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	
* X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	76	
* X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	236	
* X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	8	
* X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	2	
* XX006534	SANITARY SEWER, PVC, 10" IN 16" CASING PIPE	L. SUM	1	

\* SPECIAL PROVISIONS  
Δ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
DATE \_\_\_\_\_ CHECKED BY \_\_\_\_\_

CADD FILE: /4690/FBarrg\_4690.dgn  
PLOTTED: 8/04/28

H.M. & G. INC. 4690