

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
331	*	JACKSON	258	28
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*(12-112N,1-5,TS-3,B-1				

MEDIAN AND CURB AND GUTTER SCHEDULE

LOCATION	MEDIAN REMOVAL	CONCRETE MEDIAN SURFACE TYPE A, 4"	COMBINATION CURB AND GUTTER REMOVAL	COMBINATION CURB AND GUTTER B-6.12	COMBINATION CURB AND GUTTER B-6.24	COMBINATION CURB AND GUTTER M-6.06	PROTECTIVE COAT	SUB-BASE GRANULAR MATERIAL TYPE A, 4"
	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ YD	SQ YD
ILLINOIS 13								
25+85 TO 28+13 (ENT)			270			1157	334	527
25+85.6 TO 37+42.5				85			15	29
28+36 (ENT) TO 29+40 (ENT)			225					
29+63 (ENT) TO 30+02 (ENT)			121		98		17	34
30+23 TO 30+64 (ENT)			126		90		16	31
30+82 (ENT) TO 31+02 (ENT)			127		87		16	30
31+32 (ENT) TO 32+16 (ENT)			178		91		16	31
32+42 (ENT) TO 32+75 (ENT)			113		89		16	31
33+11 (ENT) TO 33+50 (ENT)			152		68		12	23
33+70.7 TO 37+44			380		82		15	28
38+71.9 TO 46+43.2			576	577		771	223	351
40+67 TO 46+43.22 LT							103	199
ILLINOIS 13 (EASTBOUND)								
46+48.39 TO 51+00 LT				473	452		80	156
46+48.4 TO 52+27.4						579	167	264
53+57.7 TO 54+62.3	1194							
53+58 TO 57+05 RT								
53+79.4 TO 57+04.7 RT						328	44	98
53+84.9 TO 57+59.7		4057					451	
58+38.1 TO 58+65.6		608					68	
ILLINOIS 13 (WESTBOUND)								
0+00 TO 5+83.2 RT						583	168	266
0+71 TO 6+03.09 RT	4550		72					
46+00 TO 46+43.22 RT			43		43		13	20
53+75 TO 57+22 LT								
53+76.7 TO 57+21.6 (MEDIAN)						345	100	157
65+75 TO 67+93.75 RT						20	6	9
67+61.94 TO 67+93.75 RT			34					
OLD MAIN								
0+83.9 RT TO 25+85 (IL 13) LT			71			53	15	24
GLENVIEW								
9+19.5 (GLENVIEW) TO 38+71.9 (IL 13)						50	14	23
9+19 LT TO 38+77 LT (IL 13)			60					
EMERALD								
52+27.4 (IL 13 EB) TO 8+89.1 (EMERALD)						95	27	43
52+57 (IL 13 EB) TO 8+89 RT (EMERALD)			92					
8+89 LT (EMERALD) TO 53+47 (IL 13 EB)			116			76	22	35
SYCAMORE								
5+83.2 RT (IL 13 WB) TO 11+59.9 RT (SYCAMORE)						133	38	61
6+19 (IL 13 WB) TO 11+60 RT (SYCAMORE)			102					
11+60 LT (SYCAMORE) TO 6+58 RT (IL 13 WB)			102					
11+60 LT (SYCAMORE) TO 53+62.2 RT (IL 13 WB)						82	24	37
6+41 TO 6+34.51 RT (SIDEWALK RAMP)			7					
TOTALS	5744	4665	3440	1719	3987	328	2020	2507