

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
331	*	JACKSON	258	29
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	
*(12-112N,1-5,TS-3,B-1				

SURFACING AND SHOULDER SCHEDULE

LOCATION	BITUMINOUS SURFACE REMOVAL, 1-1/2"	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	PCC SURFACE REMOVAL BUTT JOINT	PCC SURFACE REMOVAL	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, N105, IL-19, 0	POLYMERIZED LEVELING BINDER (MACHINE METHOD) SUPERPAVE N105	TEMPORARY RAMP	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	PAVED SHOULDER REMOVAL	BITUMINOUS SHOULDERS SUPERPAVE, 8"
	SQ YD	SQ YD	SQYD	SQ YD	TON	TON	TON	SQ YD	TON	GAL	SQ YD	SQ YD
ILLINOIS 13												
22+79 TO 26+20 (EB AND TURN LANE)		1825			159				2.8	170.5		
23+79 TO 24+84								27				
25+60.4 TO 37+37.7							88		1.8	106		
26+15 TO 26+20 RT (EB)								7				
26+20 TO 39+74.9					455				8.1	487.8		
26+20 TO 45+50		5147										
38+59 TO 45+50							155		1.4	82.9		
38+76.51 TO 46+43.22 LT											681	
39+69.87 TO 39+74.87 (EB)								7				
39+74.9 TO 40+69					42				0.8	45.2		
40+64 TO 40+69 (WB)	2565				450			20				
40+69 TO 45+50						7			8.0	482.3		
40+69 TO 46+43.22		746										
45+50 TO 46+43.22												
ILLINOIS 13 (EASTBOUND)												
46+48.39 TO 47+20.03		191										
46+48.39 TO 52+57.34 LT											541	
46+48.39 TO 53+04.8	1574				221	1044			15.8	945.2		
47+19.80 TO 53.57.7												
53+04.8 TO 57+04.7					226				4.0	240.9		
53+09 TO 62+68						792			11.8	710.4		
53+47.24 TO 57+65.33 LT											372	
53+46.7 TO 57+40.3 LT												403
53+57.7 TO 57+04.7	1068											
56+48.88 TO 57+73.35 RT											55	
56+96.65 TO 57+04.65								20				
57+71.6 TO 65+56.4	2273											
58+17.8 TO 65+56.02 LT												832
58+18.35 TO 61+08.00 LT											255	
58+26.43 TO 60+25.00 RT											88	
58+71.45 TO 58+76.45								13				
58+71.6 TO 65+56.4					307				5.5	328.9		
61+00 TO 65+56 LT											289	
62+68.3 TO 65+56.02									1.2	71.1		
65+51.36 TO 65+56.36								20				
ILLINOIS 13 (WESTBOUND)												
0+00 TO 0+71.59		382										
0+00 TO 6+58.5					295	1707			21.1	1264.4		
0+66.45 TO 0+71.45								14				
0+71.5 TO 6+19.4 RT											487	
5+76.10 TO 6+58.20	160											
53+07 TO 62+60												
53+07.30 TO 53+55.30	100								5.0	298.2		
53+07.3 TO 57+21.6					139				2.5	149.1		
53+62.24 TO 57+74.09 LT												470
53+64.9 TO 57+83.7 RT											372	
54+59.63 TO 57+75.00 LT											140	
57+12.58 TO 57+21.6								22				
58+26.43 TO 62+17.00 LT											174	
58+38.5 TO 63+00 RT											410	
58+51.8 TO 67+75 RT												761
58+87.40 TO 58+99.40								30				
58+87.4 TO 67+93.8					374				9.2	549.6		
62+60 TO 62+65								41				
62+60 TO 63+00		145										
62+60.2 TO 67+74.8									1.1	64.1		
62+83.72 TO 67+83.72	2347							90				
63+00 TO 67+93.80												
63+00 TO 67+81.8 RT											256	
GLENVIEW												
9+75 TO 9+63				206								
EMERALD												
8+89.08 TO 8+94.08								20				
8+89.08 TO 8+96.08			32									
9+76.9 TO 8+89.1					53	230			2.9	170.1		
SYCAMORE												
10+52 TO 11+52.90	585											
10+66.5 TO 11+59.9					51	204			2.7	162		
11+54.91 TO 11+59.91								20				
TOTALS	10672	8436	32	206	2772	4659	390	351	106	6329	4120	2466

Z:\23\2006\98827\98827.dwg
 11/11/06 11:11:11 AM
 11/11/06 11:11:11 AM