

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
331	*	JACKSON	258	31
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	
*(12-1)2N,I-5,TS-3,B-1				

SIDEWALK SCHEDULE

LOCATION	SIDEWALK REMOVAL	PCC SIDEWALK, 5"	PROPOSED WIDTH
	SQ FT	SQ FT	FEET
ILLINOIS 13			
25+63.70 TO 25+75.00 LT (RAMP)		51	6
25+75.00 TO 28+12.81 LT	931	1189	5
26+10.72 TO 26+08.71 LT (TO OLD MAIN)	43	43	6
26+26.75 LT (ENTRANCE TO SI SURGICAL APPLIANCE)	46	46	6
27+11.87 TO 27+21.65 LT (ENTRANCE TO SI SURGICAL APPLIANCE PARKING LOT)	54	54	3.6
28+12.8 LT TO 28+18.88 LT (RAMP)		33	6
28+42.74 LT TO 28+50.00 LT (RAMP)		33	5
28+50.00 TO 29+47.18 LT	464	389	4
29+47.18 TO 29+54.5 LT (RAMP)		34	5
29+84.47 LT TO 29+90.09 LT (RAMP)		35	5
29+90.09 TO 30+03.19 LT	119	52	4
30+03.19 TO 30+09.84 LT (RAMP)		32	5
30+36.76 TO 30+45.15 LT (RAMP)		34	5
30+45.15 TO 30+61.16 LT	124	64	4
30+61.16 TO 30+67.66 LT (RAMP)		32	5
30+86.60 TO 30+90.27 LT (RAMP)		43	5
30+94.27 TO 31+06.40 LT	111	49	4
31+06.40 TO 31+13.22 LT (RAMP)		33	5
31+45.07 TO 31+50.86 LT (RAMP)		34	5
31+50.86 TO 32+18.00 LT	294	269	4
32+18.00 TO 32+24.62 LT (RAMP)		32	5
32+50.90 TO 32+58.55 LT (RAMP)		33	5
32+58.55 TO 32+68.15 LT	96	38	4
32+68.45 LT TO 32+74.82 LT (RAMP)		32	5
33+11.59 TO 33+17.59 LT (RAMP)		32	5
33+17.59 TO 33+54.49 LT	204	148	4
33+54.49 TO 33+61.11 LT (RAMP)		32	5
34+02.37 TO 34+11.28 LT (RAMP)		35	5
34+11.28 TO 34+25.00 LT	84	55	4
37+14.29 LT (ILLINOIS 13 RAMP)	65	33	5
39+87.95 TO 40+67.28 LT (ADJACENT TO FRONTAGE ROAD)	337	531	6
40+67.28 TO 46+43.20 LT (ADJACENT TO MURDALE PARKING LOT)		3466	6
ILLINOIS 13 (EASTBOUND)			
46+48.56 TO 51+43.19 LT (ADJACENT TO MURDALE PARKING LOT)		3000	6
EMERALD			
6+40.06 TO 6+44.63 RT (RAMP TO FRONTAGE ROAD)		46	6
6+44.63 TO 8+83.14 RT (WEST SIDE OF PARKING LOT)		740	5
6+64.49 TO 6+84.01 RT (ADJACENT TO EMERALD)		130	5
6+84.01 TO 9+48.14 RT (ADJACENT TO EMERALD)		1659	7
SYCAMORE			
10+76.82, 51.41' LT TO 10+83.51, 43.89' LT		70	7
TOTALS	2972	12661	

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
ILLINOIS 13				
LT 22+79 to 25+50.00	0	0	0	0
LT 25+50 to 38+00	1903	1427	0	1427
LT 38+00 to 53+00	1172	879	1802	-923
LT 53+00 to 65+56.43	833	625	4932	-4307
RT 46+48.39 to 52+50	514	385	1011	-625
RT 52+50 to 67+83.72	1307	980	2479	-1499
EMERALD				
LT 8+75 to 9+75	60	45	134	-89
RT 6+50 to 9+50	220	165	264	-99
SYCAMORE				
LT 10+75 to 11+75	12	9	127	-118
RT 10+50 to 11+50	18	14	377	-363
TOTALS	6040			-6596

GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE A	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (FLARED)	GUARDRAIL REMOVAL
	FOOT	EACH	EACH	EACH	EACH	FOOT
ILLINOIS 13 (EASTBOUND)						
58+11.03 TO 58+41.18 LT			1			
58+17.09 TO 59+29.12 LT						113
58+27.60 TO 59+40.27 RT						113
58+41.18 TO 59+40.14 LT	100					
59+40.14 TO 59+89.63 LT				1		
ILLINOIS 13 (WESTBOUND)						
55+92.15 TO 56+42.44 RT				1		
56+42.44 TO 57+42.81 RT	100					
56+72.03 TO 57+72.02 LT						100
56+82.66 TO 57+83.03 RT						100
57+42.81 TO 57+73.43 RT			1			
64+27.57 TO 64+64.98 RT					1	
64+64.98 TO 67+62.45 RT	287.5					
67+62.45 TO 67+74.95 RT		1				
TOTALS	487.5	1	2	2	1	426