

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
331	*	JACKSON	258	32
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	
*(12-112N,I-5,TS-3,B-1				

### SEEDING AND EROSION CONTROL SCHEDULE

LOCATION	SEEDING CLASS 1B	SEEDING CLASS 7	MULCH METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	EROSION CONTROL BLANKET	INLET & PIPE PROTECTION	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER	TEMP. EROSION CONTROL SEEDING	STONE DUMPED RIP RAP CLASS A3	STONE RIP RAP CLASS A3 (SPECIAL)	STONE RIP RAP CLASS A4	FILTER FABRIC
	ACRE	ACRE	ACRE	POUND	POUND	POUND	TON	SQ YD	EACH	EACH	FOOT	POUND	SQ YD	SQ YD	SQ YD	SQ YD
<b>ILLINOIS 13</b>																
26+60 (IL 13) TO 37+44 (IL 13) LT	0.43	0.43	0.00	69	52	52	0.9	2067			477	129				
<b>ILLINOIS 13 (EASTBOUND)</b>																
38+34 (IL 13) TO 52+59 (IL 13 EB) LT	1.30	1.30	0.96	208	156	156	2.6	1639	3	3		390	64	164		
40+14.94 LT													26			
48+10.21 LT																
58+65 TO 62+60 RT (MEDIAN)	0.23	0.23	0.23	37	28	28	0.5		2			69				
54+00 TO 66+30 LT	1.10	1.10	1.01	176	132	132	2.2	430	1	6	773	330			104.5	104.5
57+17 TO 58+26 (BRIDGE)															1125.5	1125.5
<b>ILLINOIS 13 (WESTBOUND)</b>																
46+00 (IL 13) TO 6+56 (IL 13 WB) RT	0.3	0.30	0.15	48	36	36	0.6	737	1	2		90				
0+75 TO 6+08 RT																1727
53+69 TO 56+00 RT	0.11	0.11	0.11	18	13	13	0.2					33				
53+69 TO 58+42 RT										3					2705	
57+60 TO 58+58 (BRIDGE)															635	635
58+42 TO 67+92 RT	0.8	0.80	0.80	128	96	96	1.6				774	240				
<b>GLENVIEW</b>																
9+00 TO 9+64, LT	0.03	0.03	0.03	4.8	4	4	0.1					9				
<b>EMERALD</b>																
6+40 TO 9+64, RT	0.41	0.41	0.39	66	49	49	0.8	93				123				
6+40 TO 9+64, LT	0.11	0.11	0.07	18	13	13	0.2	203				33				
8+85 TO 9+40 LT														123		
9+40.91 RT													50			
<b>SYCAMORE</b>																
10+67 TO 11+60, LT	0.10	0.10	0.10	16	12	12	0.2					30				
10+67 TO 11+60, RT	0.04	0.04	0.01	6	5	5	0.1	163				12				
<b>OLD MAIN</b>																
0+36 TO 0+84, RT	0.02	0.02		3	2	2	0.0	111				6				
<b>TOTALS</b>	<b>5.0</b>	<b>5.0</b>	<b>3.9</b>	<b>797</b>	<b>598</b>	<b>598</b>	<b>10.0</b>	<b>5443</b>	<b>7</b>	<b>14</b>	<b>2024</b>	<b>1494</b>	<b>140</b>	<b>4719</b>	<b>1865</b>	<b>1865</b>

2/15/2009 9:00:00 AM C:\Users\j... \Public\98827.dgn