

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
881	32I	SALINE	22	4
STA. 93+73.86		TO STA.106+92.23		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES (CONT)

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	QUANTITY
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3534
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1319
48100100	AGGREGATE SHOULDERS, TYPE A	TON	200
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	443
50105220	PIPE CULVERT REMOVAL	FOOT	40
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	40
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	464
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	20.6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7213
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	250
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	155
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	20.6
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7213
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	250
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	17

URBAN
80% FED / 20% STATE
SALINE COUNTY
ROADWAY
1000-1A

* SPECIALTY ITEMS

PLOT DATE = 2/3/2006
FILE NAME = c:\p\meta\98913\98913.dgn
PLOT NAME = 1000-1A
USER NAME = eacvppj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

SUMMARY OF QUANTITIES