CONTRACT NO. 98967

U.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
US 45	*	MASSAC	13	5

*D-9 SMART FY 06-3

PAVEMENT PATCHING SCHEDULE

(FOR INFORMATION ONLY)

	SOUTHBOUND				CENTER TURN				NORTH BOUND				PARKING			
	TY I SQ. YD.	TY II SQ. YD.	TY III SQ. YD.	TY IV SQ. YD.	TY I SQ. YD.	TY II SQ. YD.	TY III SQ. YD.	TY IV SQ. YD.	TY I SQ. YD.	TY II SQ. YD.	TY III SQ. YD.	TY IV SQ. YD.	TY I SQ. YD	TY II SQ. YD	TY III SQ. YD	TY IV SQ. YD
CLASS B PATCHES, 10 INCH																
INTERSECTION (10TH AND FERRY)																
SOUTH LEG										7.3						
										7.3						
										6.0						
NORTH LEG										11.3						
										5.0						
										9.3						
									4.7							
TOTAL	0	0	0	0	0	0	0	0	4.7	46.2	0	0	0	0	0	0
PAVEMENT PATCHING, 14 INCH																
10TH	4.9															
					4.9											
					2.2											
									3.3							
									4.9							
									4.9							
		7.3														
		7.3														
						7.3										
									4.9							
9TH	4.9															
	4.9															
					4.9											
									4.9							
													3.1			
	1.8															
	4.9															
	4.9															
	4.9															
	4.9															
8TH	4.9															
		7.3														
						7.3										
									4.9							
									4.9							
													3.1			
	4.9															
	4.9															
					4.9											
									4.9							
									4.9							
													3.1			
					4.9											
					4.9											
					4.9											
									4.9							
									4.9							
													3.1			
7TH	4.9															
	4.9															
					4.9											
	4.9															
		6.1														
					4.9											
6TH	4.9															
	4.9															
	4.9															
	4.9															
					4.9											
						6.1										
										6.1						
	4.9															
	4.9															
						7.3										
										6.1						
									4.9							
		6.1														
					4.9											
									3.6							
									4.9							
0													3.1			
	4.9															
5TH																
INTERSECTION (5TH AND FERRY)				23.3												
TOTAL	99.8	34.1	0.0	23.3	51.2	28.0	0.0	0.0	65.7	12.2	0	0	15.5	0	0	0

PLOT DATE = 2/2/2006
FILE NAME = c:\pwworking\d06\d98967\d98240bsh.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = coleamm