



ELECTRICAL NOTES

1. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 (MOST CURRENT ISSUE IN FORCE), THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES, AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL. LISTING (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE SHALL NOT BE PERMITTED.
2. CONTRACTOR SHALL COORDINATE NEW WORK AND ANY POWER OUTAGES TO EXISTING EQUIPMENT WITH THE RESPECTIVE USER PERSONNEL & THE AIRPORT MANAGER.
3. ALL EQUIPMENT NOT LABELED AS EXISTING IS NEW.
4. PROVIDE A WEATHERPROOF ENGRAVED PHENOLIC OR PLASTIC LEGEND PLATE FOR THE SAFETY SWITCH AT THE RESPECTIVE GATE OPERATOR LABELED "GATE NO. 1, 120 VAC, FED FROM TERM BLDG PANEL B".
5. FURNISH AND INSTALL A #12 AWG EQUIPMENT GROUND WIRE FROM THE GATE OPERATOR TO THE CARD READER UNIT IN THE EXISTING CONTROL WIRING CONDUIT.
6. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS.
7. WORK SHOWN ON THIS SHEET SHALL BE PAID FOR UNDER ITEM AT109200.

WORK SHOWN ON THIS SHEET IS FOR BID ALTERNATE NO. 2

GATE NO. 1 ELECTRICAL ONE LINE

BY	
REVISION	
DATE	

MT. VERNON AIRPORT

 MT. VERNON, ILLINOIS
 I.L. PROJ.: MVN-3539 A.I.P. PROJ.: 3-17-0074-B12

HEL Project No. 819-06RWYD	12/02/05
File Name: E-604.DWG	KNL
Scale: NONE	NY
Date: 12/16/05	CAH
LAYOUT	12/14/05
DRAWN	
REVIEWED	

HANSON

 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

RUNWAY 15-33
 P.F.C. OVERLAY
 GATE NO. 1
 ELECTRICAL ONE LINE

MAR 30, 2006 2:25 PM DFE
 I:\AIRPORTS\MV\VERNON\819-06RWYD\AIRPORT\SHEETS\E-604.DWG - Work-FLR