

80% FED
20% STATE

FAP 760 (1L32)
RURAL 2L/2W
MINOR ARTERIAL
PIATT COUNTY
ROADWAY
0005
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20400800	FURNISHED EXCAVATION	CU YD	66	66
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	15
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15
25100630	EROSION CONTROL BLANKET	SQ YD	790	790
28000400	PERIMETER EROSION BARRIER	FOOT	300	300
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	97017	97017
40600370	LONGITUDINAL JOINT SEALANT	FOOT	50535	50535
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160
40600990	TEMPORARY RAMP	SQ YD	3417	3417
40602965	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N50	TON	19175	19175
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	12073	12073
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	12073	12073
40800025	BITUMINOUS MATERIALS (PRIME COAT)	POUND	9847	9847

* SPECIALTY ITEM

MODEL: Default
FILE NAME: T:\TGC\Business\Clients\Kassak\20-169_PTB_197-028 IL 32100 CAD\02 CAD\02 Sheets\Phase2\057092-500-01.dgn



USER NAME = MatthewToussaint	DESIGNED - RW	REVISED -
PLOT SCALE =	DRAWN - RW	REVISED -
PLOT DATE = 2/1/2023	CHECKED - MRT	REVISED -
	DATE - 01/31/2023	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
760	(10,M-15D,27,205,206)RS-2	PIATT	93	3
P-95-019-11		CONTRACT NO. 70992		
ILLINOIS FED. AID PROJECT				