



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 12, 2023

SUBJECT: CH 16 (Tuller Road)  
Section 19-00163-00-BR  
Saline County  
Contract No. 99681  
Item 158  
April 28, 2023 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Special Provision Index**
- 2. Revised page 1 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

**INDEX OF SHEETS**

Item	Page Number
Description of Work	1
<del>Start Date/Completion Date</del>	<del>4</del>
Traffic Control	1
Portable Changeable Message Signs	2
Removal of Existing Structure	2
Earth Excavation	3
Seeding, Class 2 (Special)	3
Stone Dumped Riprap, Class A4	3
Aggregate Surface Course, Type A	4
Status of Utilities to be Adjusted	4
Traffic Control Plan – Sign Locations	5
Borings	6
Insurance	14
404 Permit	15

**STATE OF ILLINOIS**  
**SPECIAL PROVISIONS**

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2022, the latest edition of the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures for Materials" in effect on the date of invitation of bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the proposed improvement designated as Section 19-00163-00-BR and in case of conflict with any part or parts of said specifications, the said Special Provisions shall take precedence and shall govern.

**Description of Work:**

The proposed work on Tuller Road (CH 16) consists of the removal of an existing arch culvert and construction of 1260 Square Feet of Precast Prestressed Concrete Bridge Deck, 21" Depth, supported on pile bent abutments, reconstruction of approaches, 90 feet of Steel Railing, Type S1 along with other related work necessary to complete the project.

~~**Start Date/Completion Date:**~~

~~The Contractor shall not be allowed to close the road until the beck beams have been fabricated and are ready to ship and all materials are available to complete construction. Road Closure shall not begin until June 12, 2023, and the Contractor shall be required to complete the project within 30 Calendar Days from the date the Contractor begins work.~~

**Traffic Control:**

Traffic Control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual for Uniform Traffic Control Devices for Street and Highways, these Special Provisions, and special details and Highway Standards contained herein.

Special attention is called to Articles 107.09, 107.14 and 107.15 of the Standard Specifications for Road and Bridge Construction, the following Highway Standards relating to traffic control, and the Special Provisions.

Highway Standards: 701901-08                      BLR 21-9