

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	URBAN	QUANTITIES		
			90% FED. 10% STATE	CIVIL	LIGHTING	SURVEILLANCE
			QUANTITY	J000	Y030-1E	Y032-1F
82106100	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT (INSTALL ONLY)	EACH	842	0	842	0
82107110	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	366	0	366	0
82107310	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	8	0	8	0
83050860	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-6 FT. MAST ARMS	EACH	2	0	2	0
83600200	LIGHT POLE FOUNDATION, 24" DIA.	FOOT	0	0	0	0
83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	1,955	0	1,955	0
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	22	0	22	0
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	630	0	630	0
84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	24	0	24	0
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	8	0	8	0
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	8	0	8	0
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	8	0	8	0
86300400	CONTROLLER CABINET TYPE IV	EACH	2	0	0	2
87000212	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 2 AND NO. 6 GROUND	FOOT	2,300	0	0	2,300
87302405	ELECTRIC CABLE AERIAL SUSPENDED, COMMUNICATIONS, NO. 18 3-PAIR	FOOT	0	0	0	0
87502100	TRAFFIC SIGNAL POST, PAINTED STEEL 2.5 FT	EACH	7	0	0	7
87502207	TRAFFIC SIGNAL POST, PAINTED STEEL 5 FT.	EACH	20	0	0	20
87502210	TRAFFIC SIGNAL POST, PAINTED STEEL 7 FT	EACH	9	0	0	9
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	0	0	12
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	9	0	0	9
87900200	DRILL EXISTING HANDHOLE	EACH	18	0	0	18
88600300	DETECTOR LOOP, TYPE III	FOOT	1,809	0	0	1,809
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3,886	0	0	3,886
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	3,605	0	0	3,605
X0321973	MODIFY EXISTING SERVICE INSTALLATION	EACH	2	0	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	0	0	0	0
X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	147,009	0	0	147,009
X0322920	COMMUNICATIONS CABINET AND EQUIPMENT	EACH	1	0	0	1
X0323360	WOODEN POLE REMOVAL	EACH	103	0	155	8
X0323363	ELECTRIC CABLE IN CONDUIT, NO. 12 3/C	FOOT	5,134	0	0	5,134
X0323364	ELECTRIC CABLE IN CONDUIT, NO. 19 6/C	FOOT	2,926	0	0	2,926
X0324790	ELECTRIC CABLE IN CONDUIT, NO. 19 12/C	FOOT	536	0	0	536



Rev. 4-19-05

REVISIONS	
NAME	DATE
REVISION #4	3/24/05
REVISION #1	12/17/04

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: October 29, 2004

DRAWN BY: CJM
CHECKED BY: JPC

m:\p\4630\electr\6-Civil\20-Summary 2-5002004-2.dwg