

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	COOK		2C
STA.	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
* (2021-922 PT. 1,2 & 2122-921 PT. 1) R-4			

**SHEET COMM-45:**

- FIBER OPTIC SPLICE, LATERAL IN HH4501 SHOULD BE DELETED.
- TWO (2) 2" CNC AND 48-FIBER CABLE ALONG 35TH STREET SHOULD BE DELETED.

**SHEET COMM-46:**

- 1/4" CNC BETWEEN TOWER WK1 (CABINET DR-3A) TO HH4602 SHOULD BE DELETED.
- 6-FIBER CCTV CABLE BETWEEN TOWER WK1 (CABINET DR-3A) AND HH4602 SHOULD BE DELETED.
- 1/4" CNC BETWEEN TOWER WK1 (CABINET DR-3A) AND HH4603 SHOULD BE INSTALLED.

**SHEET COMM-47:**

- 6-FIBER CCTV CABLES ALONG THE WEST SIDE OF THE DAN RYAN EXPRESSWAY SHOULD BE DELETED.
- 6-FIBER CCTV CABLES ALONG THE EAST SIDE OF THE DAN RYAN EXPRESSWAY SHOULD BE DELETED.
- 48-FIBER CCTV CABLE SHOULD BE INSTALLED ON WEST SIDE OF DAN RYAN EXPRESSWAY. 48-FIBER CABLE SHOULD CROSS AT 31ST STREET BRIDGE USING TWO (2) 2" GSC ATTACHED TO STRUCTURE AND JOIN EAST 48-FIBER CCTV CABLE.
- 48-FIBER CCTV CABLE SHOULD BE INSTALLED ON EAST SIDE OF DAN RYAN EXPRESSWAY.

**SHEET COMM-48:**

- 6-FIBER CCTV CABLE FROM CABINET DR-2B SHOULD BE SPLICED TO 48-FIBER CCTV CABLE IN HH4802.
- 6-FIBER CCTV CABLE ALONG THE EAST SIDE OF THE DAN RYAN EXPRESSWAY SHOULD BE DELETED.
- TWO (2) 48-FIBER CCTV CABLE SHOULD BE INSTALLED ON EAST SIDE OF DAN RYAN EXPRESSWAY.
- NORTH OF JUNCTION BOX 4803, TWO (2) 48-FIBER CCTV CABLES SHOULD BE INSTALLED IN THE 2" GSC WITH THE 96-FIBER BACKBONE CABLE.

**SHEET COMM-49 AND COMM-50:**

- TWO (2) 48-FIBER CCTV CABLES SHOULD BE INSTALLED IN THE 2" GSC WITH THE 96-FIBER BACKBONE CABLE.

**SHEET COMM-51:**

- TWO (2) 48-FIBER CCTV CABLES SHOULD BE INSTALLED IN THE 2" GSC WITH THE 96-FIBER BACKBONE CABLE. THE TWO (2) 48-FIBER CCTV CABLES SHOULD BE TERMINATED IN THE NORTH I-55 COMMUNICATION SHELTER (RO).

**SHEET COMM-56:**

- DELETE AND REPLACE WITH SHEET 2C DRAWING

**SHEET COMM-62 THROUGH COMM-68:**

- DELETE 6F CABLES AS SHOWN.
- INSTALL ONE EACH 48F TRUNK CABLE ON BOTH NORTHBOUND AND SOUTHBOUND SIDES OF ROAD (NEW); INSTALL 6F CABLE FROM CCTV CABINET TO COMM VAULT AND 48F TRUNK CABLE; SPLICE 6F CABLE TO 48F CABLE.
- DO NOT INSTALL 6F CABLE AT FUTURE CAMERA SITES

**SHEET COMM-69:**

- INSTALL ONE EACH 48F TRUNK CABLE ON BOTH NORTHBOUND AND SOUTHBOUND SIDES OF ROAD (NEW); TERMINATE IN SHELTER

**SHEET COMM-70 AND COMM-71:**

- DELETE VIDEO DISTRIBUTION AMPLIFIERS AND JPEG CAPTURE DEVICES; INSTALL COAXIAL CABLE FROM VIDEO PATCH PANEL TO VIDEO ENCODER

**SHEET COMM-81 THROUGH COMM-84:**

- DELETE DRAWING.

**SHEET COMM-90, COMM-96, AND COMM-97:**

- DELETE VIDEO DISTRIBUTION AMPLIFIERS AND JPEG CAPTURE DEVICES.

**SHEET COMM-98 THROUGH COMM-100:**

- DELETE VIDEO DISTRIBUTION AMPLIFIERS AND JPEG CAPTURE DEVICES; INSTALL COAXIAL CABLE FROM VIDEO PATCH PANEL TO VIDEO ENCODER

**SHEET COMM-107 THROUGH COMM-109:**

- DELETE DRAWING.

**SHEET COMM-110 AND COMM-112:**

- DELETE 6F CABLE FROM TERMINATION TABLES; ADD 48F TERMINATION TABLES

**SHEET COMM-115 AND COMM-116:**

- DELETE PATCHES TO CCTV FIBERS.

**SHEET COMM-117:**

- DELETE 6F CABLE FROM TERMINATION TABLES; ADD 48F TERMINATION TABLES

**SHEET COMM-118 AND COMM-119:**

- DELETE PATCHES TO CCTV FIBERS.

**SHEET COMM-120:**

- DELETE DRAWING.

**SHEET COMM-121 AND COMM-122:**

- DELETE PATCHES TO CCTV FIBERS.

**SHEET COMM-123:**

- DELETE DRAWING.

**SPARE 1/4" CNC CONDUIT REMOVAL**

- 1) DELETE (2) OF THE SPARE 1/4" CNC CONDUITS THAT RUN WITH THE 96F BACKBONE ON ALL COMM SHEETS. ONE SPARE 1/4" CNC CONDUIT WILL BE INSTALLED ON EACH SIDE OF THE DAN RYAN. QUANTITIES IN THE SUMMARY OF QUANTITIES HAVE BEEN MODIFIED TO REFLECT THIS REVISION.

**48F CCTV CABLE RUN**

- 1) ALL 48F CCTV CABLE WILL BE INSTALLED IN THE SAME 1/4" CNC CONDUIT AS THE 48F DISTRIBUTION CABLE

**TEMPORARY DETECTION**

- 1) THE TEMPORARY DETECTION SYSTEM ITEMS HAVE BEEN DELETED
- 2) SHEETS SYS-07, DT-53, DT-54, DT-55 HAVE BEEN DELETED
- 3) QUANTITIES IN THE SUMMARY OF QUANTITIES HAVE BEEN MODIFIED TO REFLECT THE DELETION OF THIS WORK. REVISED PLAN SHEETS WILL NOT BE PROVIDED TO THE CONTRACTOR



REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 94/90 (DAN RYAN EXPRESSWAY) 31st STREET to I-57
NAME	DATE	
		DESIGN CHANGES AND CLARIFICATIONS  SCALE: NOT TO SCALE DATE: MARCH 24, 2005 DRAWN BY: DHI CHECKED BY: MJL/JEZ

**NEW SHEET** 3/24/05

m:\P\04069\04069\01-CORR\Contract 2 - Revisions for April Letting\2B.dgn 03/24/2005 03:28:06 PM