

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS	NO.
90/94	2003-0311	COOK	976	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS		FED. AID PROJECT		

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	90% FED. 10% STATE	QUANTITIES		
			URBAN	CIVIL	LIGHTING	SURVEILLANCE
			QUANTITY	J000	Y030-1E	Y032-1F
50300225	CONCRETE STRUCTURES	CY	0.0	0.0	0.0	0.0
42001300	PROTECTIVE COAT	SQ YD	98	98	0	0
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CY	10	10	0	0
50300510	RUSTICATION FINISH	50 FT	0.0	0.0	0.0	0.0
50800205	REINFORCEMENT BARS, EPOXY COATED	LBS	0	0	0	0
54201267	PIPE CULVERTS, TYPE 2, RCCP, 12"	FOOT	67	0	67	0
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	6	0	6	0
60600605	CONCRETE CURB, TYPE B	FOOT	0	0	0	0
60603800	COMBINATION CURB AND CUTTER, TYPE B-6.12	FOOT	0	0	0	0
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1	0	0
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	133	133	0	0
66400305	CHAIN LINK FENCE, 6'	FOOT	982	982	0	0
66410300	CHAIN LINK FENCE REMOVAL	FOOT	973	973	0	0
66400520	CHAIN LINK FENCE, 12'	FOOT	155	155	0	0
66407600	CHAIN LINK GATES, 6' X 12' DOUBLE	EACH	1	1	0	0
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	773	773	0	0
* 66900200	NON-SPECIAL WASTE DISPOSAL	CY	796	152	644	0
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	0	0	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10	4	6	0
67100100	MOBILIZATION	L SUM	1	0.33	0.34	0.33
* 72000100	SIGN PANEL - TYPE 1	SQ FT	266	0	0	266
* 72000300	SIGN PANEL - TYPE 3	SQ FT	179	0	0	179
** * 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	LBS	954	0	0	954
73400100	CONCRETE FOUNDATIONS	CY	4	0	0	4
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	0	0
80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	410	0	410	0
80802600	WOOD POLE, 50 FT., CLASS 2	EACH	1	0	0	1
80800300	TEMPORARY WOOD POLE, 45 FT., CLASS 4	EACH	0	0	0	0
80800400	TEMPORARY WOOD POLE, 50 FT., CLASS 4	EACH	32	0	24	8
80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	43	0	43	0
80800520	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 8 FT. MAST ARM	EACH	0	0	0	0
80800850	TEMPORARY WOOD POLE, 90 FT., CLASS 4, 15 FT. MAST ARM	EACH	22	0	22	0
81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL	FOOT	0	0	0	0

(**) SFTY - 3C
* SPECIALTY ITEMS



REVISIONS	
NAME	DATE
REVISION #4	3/24/05
REVISION #1	12/17/04

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: CJM
DATE: October 29, 2004 CHECKED BY: JPC