

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	976	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	90% FED. 10% STATE	QUANTITIES		
			URBAN	CIVIL	LIGHTING	SURVEILLANCE
			QUANTITY	J000	Y030-1E	Y032
Z0076600	TRAINEES	HR	5,000	5,000	0	0
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.33	0.34	0.33
X0324793	LIGHT TOWER SERVICE PAD, SPECIAL	50 FT	0	0	0	0
X8300575	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 16 FT. MAST ARM	EACH	0	0	0	0
X0324810	ELECTRIC SERVICE INSTALLATION, 30A, 120V	EACH	31	0	0	31
X0324252	ELECTRIC SERVICE INSTALLATION, 100A, 120/240V	EACH	3	0	0	3
X0324254	ELECTRIC SERVICE INSTALLATION, 200A, 120/240V	EACH	6	0	0	6
X0324811	ELECTRIC SERVICE INSTALLATION, 200A, 240/480V	EACH	9	0	9	0
B7000172	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4 AND NO. 6 GROUND	FOOT	174	0	174	0
B7000214	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 2 AND NO. 4 GROUND	FOOT	2,207	0	2,207	0
X8700550	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 350 MCM	FOOT	715	0	715	0
X8160145	UNIT DUCT, WITH 2-1/C NO. 2 AND 1/C NO. 2 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	6,653	0	0	6,653
X8110125	CONDUIT ATTACHED TO STRUCTURE, 4" DIA. GALVANIZED STEEL, PVC COATED	FOOT	1,350	0	1,350	0
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	1,755	1,755	0	0
X0324794	COMMUNICATIONS SHELTER, 10 X 12	EACH	1	0	0	1
X0324795	COMMUNICATIONS SHELTER, 10 X 20	EACH	1	0	0	1
X0324796	CONCRETE FOUNDATION, TYPE 2	FOOT	190	0	0	190
X8710045	FIBER OPTIC CABLE 12 FIBERS, SINGLE MODE PIGTAIL	FOOT	2,290	0	0	2,290
X8710034	FIBER OPTIC CABLE 60 FIBERS, SINGLE MODE	FOOT	30,599	0	0	30,599
X8710052	FIBER OPTIC TERMINATION PANEL, 12F	EACH	52	0	0	52
X8670100	PULLING PEDESTAL	EACH	19	0	0	19
	SIGNAL HEAD, POLYCARBONATE, LED, 1 FACE, 2 SECTION, WALL MOUNTED	EACH	0	0	0	0
X0324797	ELECTRIC CABLE IN CONDUIT, 2/C NO. 2, 1/C NO. 6 GND	FOOT	12,562	0	0	12,562
X0324798	ELECTRIC CABLE IN CONDUIT, 2/C NO. 4, 1/C NO. 6 GND	FOOT	20,065	0	0	20,065
X0324799	ELECTRIC CABLE IN CONDUIT, 2/C NO. 1/0, 1/C NO. 6 GND	FOOT	3,442	0	0	3,442
X0324800	CABINET, MODEL 334, DYNAMIC MESSAGE SIGN	EACH	5	0	0	5
X0324801	CABINET, MODEL 334, UNINTERRUPTIBLE POWER SYSTEM	EACH	0	0	0	0
X0324802	CABINET, MODEL 334 EQUIPMENT, SYSTEM DETECTOR	EACH	27	0	0	27
X0324803	CABINET, MODEL 334 EQUIPMENT, RAMP METER	EACH	14	0	0	14
X0324804	CABINET, MODEL 334 EQUIPMENT, DMS/SYSTEM DETECTOR	EACH	1	0	0	1
X0324805	CABINET, MODEL 334 EQUIPMENT, DYNAMIC MESSAGE SIGN	EACH	5	0	0	5
X0324806	CABINET, MODEL 334 EQUIPMENT, UNINTERRUPTIBLE POWER SYSTEM	EACH	0	0	0	0

7 OF 9



© Y080

REVISIONS	NAME	DATE
REVISION #4		3/24/05
REVISION #1		12/17/04

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE

DATE: October 29, 2004

DRAWN BY: CJM

CHECKED BY: JPC

03/24/2005 02:16:22 PM