F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	976	10A
STA.	TO STA.			
FED. ROAD DIST. NO. 1 ILLINOIS	FED. AID PROJECT			

62583

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	90% FED. 10% STATE URBAN QUANTITY	QUANTITIES CIVIL J000	LIGHTING Y030-1E	SURVEILLANCE Y032-1F
X8700220	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4/0 AND NO. 2 GROUND	FOOT	536	0	0	536
X8700230	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 350MCM AND NO. 3 GROUND	FOOT	2,516	0	0	2,516
X8730248	ELECTRIC CABLE IN CONDUIT NO. 18 4PR, TWISTED, SHIELDED	FOOT	1,976	0	0	1,976
X0324836	AUTOMATED TRAFFIC RECORDER CABINET	EACH	2	0	0	2
X0324697	SOIL STABILIZERS	LBS	112,152	112,152	0	0
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	41	41	0	0
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	33			
X0324837	CIRCUIT BREAKER, 2-POLE, 50-AMPERE,240 VOLT IN EXISTING METER PEDESTAL CABINET	EACH	1	0	0	1

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

REVISIONS NAME	DATE
NEW SHEET	3/24/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: CJM
DATE: October 29, 2004 CHECKED BY: JPC

m:\P40468\Elect\16-Cntr2b\Sht\Contract 2\S0020092A.sht
03/24/2005 02:11:39 PM