F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-068L	COOK	37	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62807

SUMMARY OF QUANTITIES

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	QUANTITY	DOT WORK LIGHTING Y030-1E
67100100	MOBILIZATION	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8
80700110	GROUND ROD, 3/4" DIA. X 10'-0" LENGTH	EACH	72	72
X0324667	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE	FOOT	245	245
X0324668	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE, OFFSET	FOOT	373.75	373.75
X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	6	6
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	6	6
X0324435	CLEAN EXISTING MANHOLE OR HANDHOLE	EACH	6	6
X0324662	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 1.25"	FOOT	7884	7884
84200500	REMOVE EXISTING LIGHTING UNIT AND SALVAGE	EACH	86	86

~~Q-1889~~
□ NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 47th ST (FRONTAGE ROAD)
CITY OF CHICAGO LIGHTING CONDUIT & FOUNDATIONS
WENTWORTH AVENUE

SUMMARY OF QUANTITIES

SCALE: NONE
DRAWN BY: CJM
DATE: February 11, 2005
CHECKED BY: WDS

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

\\ctechi-nt\p40468\p40468\elec\y4-cnl\9\sht\contract 9b\3\sg09b130a120.sht
02/02/2005 09:59:10 AM