



COMPLETE COMMODITY CODE NO. 05-6610-5310M

CODE NO.	MATERIALS	SIZE	QUAN.
(1) 05-6610-5310	PRE-CAST HANDHOLE	30"X36"	1
(2) 05-9075-5470	STONE 3/4" CRUSHED	BAG	5
(2) 05-5082-5330	SOND TUBE	30"	1
(2) 05-5082-5342	SOND TUBE	42"	1
(2) 05-3267-2940	CONC. REDI-MIX	CU. YD.	1/2
(2) 57-0770-0000	6" X 6" MESH	36"X10'	1
05-1452-9720	BRICK		24
02-4299-5524	FRAME MANHOLE	24"	1
02-4574-5040	COVER, MANHOLE	24"	1
09-7796-9312	GROUND ROD	3/4"X12'	1
09-2630-3240	GROUND CLAMP		1

- (1) PRE-CAST HANDHOLE SHALL INCLUDE CABLE HOOKS AND CONDUIT KNOCKOUTS.
- (2) THESE ITEMS ARE FOR POURED-IN-PLACE HANDHOLES ONLY.

**CONSTRUCTION NOTES:**

- 1. 8" BED OF STONE FOR DRAINAGE.
- 2. ALL METALLIC CONDUITS ENTERING HANDHOLE SHALL EXTEND MINIMUM 1" & MAXIMUM 3" INSIDE INNER WALL AND BE EQUIPPED WITH AN APPROVED TYPE OF THREADED GROUNDING BUSHING.

B	01-23-00	ADDED CABLE HOOKS PER COMMISSIONER MURPHY	(DC/ED)
A	12-8-95	REDRAW (CAD)	MP
	DATE	REVISION	
30" DIA. CONCRETE HANDHOLE			
CITY OF CHICAGO			
DEPT. OF STREETS AND SANITATION DIVISION OF ELECTRICAL UTILITIES			
DESIGNED BY	M. PATTON	CHECKED BY	W. CARTER
SUPERVISING ENGINEER	ET PC. DESIGN ENGINEER	ENGINEER-IN-CHARGE	DEBARTOLO
ENGINEER OF ELECTRICAL UTILITIES		UNIV. NO.	
GEN. SUPV. OF ELECTRICAL UTILITIES			867
DEPT. COMMISSIONER			
SIZE: 11"		SCALE: NONE	DATE: 12-8-95

REVISIONS	NAME	DATE

V:\citech\m\1\4\468\p\040668\elec\14-cm15-151\contract 90.3\boe095.3005.dwg  
 02/02/2005 09:09:55 AM