F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-101 I	COOK	31	5
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62842

SUMMARY OF QUANTITIES

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	QUANTITY	DOT WORK LIGHTING YC30-1E
67100100	MOBILIZATION	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	3	3
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	205.6	205.6
80700110	GROUND ROD, 3/4" DIA. X 10'-0" LENGTH	EACH	40	40
X0324667	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE	FOOT	180	180
X0324668	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE, OFFSET	FOOT	65	65
X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	17	17
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	2	2
□ X0324435	CLEAN EXISTING MANHOLE OR HANDHOLE	EACH	2	2
X0324662	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 1.25"	FOOT	4389	4389
X0324934	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 2"	FOOT	196	196
X0320001	PVC CONDUIT IN TRENCH, 2" DIA. (SCHEDULE 40)	FOOT	61	61
X0324478	PVC CONDUIT IN TRENCH, 3" DIA. (SCHEDULE 40)	FOOT	74	74
81000600	CONDUIT IN TRENCH, 2" DIA. GALVANIZED STEEL	FOOT	10	10
X0324935	CONDUIT ELBOW, 1.25' DIA. GALVANIZED STEEL	EACH	1	1
X0329863	INTERCEPT EXISTING CONDUIT	EACH	1	1
X0324354	TRENCH AND BACKFILL WITH SCREENING AND/OR SAND	FOOT	145	145
X8950075	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1	1
84200500	REMOVE EXISTING LIGHTING UNIT AND SALVAGE	EACH	47	47
X0324434	REMOVE EXISTING STREET LIGHTING UNIT FOUNDATION	EACH	27	27

□ NON-PARTICIPATING
~~O-1080~~

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROADS)
CITY OF CHICAGO LIGHTING CONDUIT & FOUNDATIONS
WELLS STREET AND WENTWORTH AVENUE

SUMMARY OF QUANTITIES

SCALE: NONE
DRAWN BY: CJM
DATE: February 11, 2005
CHECKED BY: WDS

\\cteeit-nt\vol0\468\p\0468\elect\4-ctt-9\sht\contract 9of2\sq03\20012\s.sht
02/02/2005 09:30:58 AM