

PAVEMENT PATCHING SCHEDULE

F.A.P. RILEY	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	*	LIVINGSTON	205	20
STA.		TO STA.		
CONTRACT NO. 66261				
• 25 RS-2 & 26 RS-4				

LOCATION	SIDE	LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)	PARTIAL DEPTH PATCHING			CLASS B PATCHES				PAVEMENT FABRIC (SQ YD)
					BITUMINOUS CONCRETE REMOVAL (SQ YD)	BITUMINOUS MIXTURE FOR PATCHING (TON)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	TYPE II 10" (SQ YD)	TYPE IV 10" (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS 1 1/2" (EACH)	
240+00.00	LT	20	12	240					26.67	64.0	20	26.7
240+00.00	RT	20	12	240					26.67	44.0	20	26.7
249+16.08 (STAGE I)	RT	71.8	4	287.2					31.91	80.00	4	31.91
249+16.08 (STAGE II)	LT	71.8	20	1436.0					159.56	40.00	36	159.56
255+60.00	LT	6	12	72				8.00		30.0	20	
255+60.00	RT	6	12	72				8.00		24.0	20	
255+75.00	LT	6	12	72				8.00		30.0	20	
255+75.00	RT	6	12	72				8.00		24.0	20	
255+88.00	RT	6	12	72				8.00		30.0	20	
255+90.00	LT	6	12	72				8.00		30.0	20	
256+65.00	LT	6	12	72				8.00		30.0	20	
256+65.00	RT	6	12	72				8.00		24.0	20	
283+61.00	LT	6	12	72				8.00		30.0	20	
283+61.00	RT	6	12	72				8.00		24.0	20	
283+76.00	LT	6	12	72				8.00		30.0	20	
293+00.00	LT	6	12	72				8.00		30.0	20	
293+00.00	RT	6	12	72				8.00		24.0	20	
313+00.00	LT	8	12	96				10.67		32.0	20	
313+00.00	RT	8	12	96				10.67		24.0	20	
317+85.90	LT	26.28	12	315.36					35.04	50.0	20	35.04
317+85.90	RT	26.28	12	315.36					35.04	24.0	20	35.04
323+00.00	RT	6	12	72				8.00		30.0	20	
323+50.00	RT	6	12	72				8.00		30.0	20	
333+50.00	RT	6	12	72				8.00		24.0	20	
334+50.00	LT	6	12	72				8.00		30.0	20	
334+50.00	RT	6	12	72				8.00		24.0	20	
335+50.00	RT	6	12	72				8.00		30.0	20	
339+00.00	LT	6	12	72				8.00		30.0	20	
339+00.00	RT	6	12	72				8.00		24.0	20	
339+30.00	LT	6	12	72				8.00		30.0	20	
339+30.00	RT	6	12	72				8.00		24.0	20	
343+30.00	LT	8	12	96				10.67		32.0	20	
343+30.00	RT	8	12	96				10.67		24.0	20	
356+00.00		6	24	144	16	1.79	1.28					
356+60.00		6	24	144	16	1.79	1.28					
357+60.00		6	24	144	16	1.79	1.28					
358+00.00		6	24	144	16	1.79	1.28					
358+40.00		6	24	144	16	1.79	1.28					
358+80.00		6	24	144	16	1.79	1.28					
359+20.00		6	24	144	16	1.79	1.28					
359+80.00		6	24	144	16	1.79	1.28					
360+80.00		6	24	144	16	1.79	1.28					
361+20.00		6	24	144	16	1.79	1.28					
361+70.00		6	24	144	16	1.79	1.28					
362+10.00		6	24	144	16	1.79	1.28					
363+10.00		6	24	144	16	1.79	1.28					
364+10.00		6	24	144	16	1.79	1.28					
364+25.00		6	24	144	16	1.79	1.28					
364+30.00		6	24	144	16	1.79	1.28					
400+00.00		6	24	144	16	1.79	1.28					
400+40.00		6	24	144	16	1.79	1.28					
400+80.00		6	24	144	16	1.79	1.28					
405+00.00		6	24	144	16	1.79	1.28					
406+25.00		6	24	144	16	1.79	1.28					
407+50.00		6	24	144	16	1.79	1.28					
407+90.00		6	24	144	16	1.79	1.28					
408+65.00		6	24	144	16	1.79	1.28					
415+00.00		6	24	144	16	1.79	1.28					
415+40.00		6	24	144	16	1.79	1.28					
415+80.00		6	24	144	16	1.79	1.28					
419+80.00		6	24	144	16	1.79	1.28					
421+30.00		6	24	144	16	1.79	1.28					
425+00.00		6	24	144	16	1.79	1.28					
433+60.00		6	24	144	16	1.79	1.28					
443+60.00		6	24	144	16	1.79	1.28					
453+00.00		6	24	144	16	1.79	1.28					
454+00.00		6	24	144	16	1.79	1.28					
455+00.00		6	24	144	16	1.79	1.28					
456+50.00		6	24	144	16	1.79	1.28					
460+50.00		6	24	144	16	1.79	1.28					
461+75.00		6	24	144	16	1.79	1.28					
463+75.00		6	24	144	16	1.79	1.28					
464+25.00		6	24	144	16	1.79	1.28					
464+75.00		6	24	144	16	1.79	1.28					
465+25.00		6	24	144	16	1.79	1.28					
465+75.00		6	24	144	16	1.79	1.28					
466+25.00		6	24	144	16	1.79	1.28					
TOTAL					704	78.76	56.32	226.67	314.89	1050	660	314.89
PAY TOTAL					704	79	56*	227	315	1050	660	315

* NOT A TOTAL QUANTITY

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAP 317 (US ROUTE 24) SECTION 25 RS-2 & 26 RS-4 LIVINGSTON COUNTY SCALE: _____ DRAWN BY BANDY DATE _____ CHECKED BY _____
NAME	DATE	