

**RIPRAP SCHEDULE**

LOCATION	STONE RIPRAP, CLASS A4 (SQ YD)	FILTER FABRIC FOR USE WITH RIPRAP (SQ YD)
STATION		
249+51.77	51	51
TOTAL	51	51
PAY TOTAL	51	51

**BOX CULVERT SCHEDULE**

LOCATION	REMOVAL OF EXISTING STRUCTURE NO. 1 (EACH)	REMOVAL OF EXISTING STRUCTURE NO. 2 (EACH)	PRECAST CONCRETE BOX CULVERTS		POROUS GRANULAR EMBANKMENT (CU YD)	BOX CULVERT END SECTION	
			4' x 3' * (FOOT)	7' x 4' (FOOT)		CULVERT NO. 1 (EACH)	CULVERT NO. 2 (EACH)
STATION							
249+51.77	1			104	1044	2	
317+97.31			57				2
318+05.87		1			91		
TOTAL	1	1	57	104	1135	2	2
PAY TOTAL	1	1	57	104	1135	2	2

\* USE TO #P 701201

**PIPE CULVERT SCHEDULE**

LOCATION	PIPE CULVERT REMOVAL (FOOT)	PIPE CULVERT, CLASS D, TYPE I 18" (FOOT)
STATION	SIDE	
232+00.00	RT	39.2
269+79.74	LT	83.4
271+64.81	RT	44.2
292+07.40	LT	44.8
292+97.82	LT	40.3
TOTAL		251.9
PAY TOTAL		252

**GUARDRAIL SCHEDULE**

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) (EACH)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) (EACH)	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1 (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)
STATION TO STATION	SIDE			
357+50.92 TO 358+00.92	RT		1	1
358+00.98 TO 358+50.98	LT		1	1
360+00.89 TO 360+50.89	RT		1	1
360+50.92 TO 361+00.92	LT		1	1
472+25.09 TO 472+75.09	RT	1		1
472+34.08 TO 472+84.08	LT	1		1
474+89.12 TO 475+39.12	RT	1		1
474+98.76 TO 475+47.76	LT	1		1
TOTAL		4	4	8
PAY TOTAL		4	4	8

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION (CU YD)	FOR INFORMATION ONLY			REMARKS
		EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25% (CU YD)	EMBANKMENT (CU YD)	BALANCE (CU YD)	
STATION TO STATION					
229+55 TO 236+51.5	167	134	135	-1	
239+09.91 TO 255+52	979	783	286	497	
255+52 TO 267+75	291	233	2	231	
267+75 TO 320+55.86	2239	1791	288	1503	
320+55.86 TO 358+00	989	792	18	774	
ENTRANCES	255	204	10	194	
SIDE ROAD TR 2275	109	87		87	
SIDE ROAD TR 2300 SOUTH	135	108		52	
GUARDRAIL WIDENING	160	128	440	-312	OBTAIN 312 CU YDS OF EXCESS MATERIAL FOR OTHER BALANCE AREAS
TOTAL	5325	4259	1179	3025	
PAY TOTAL	5325	4260	1180	3025	

**TRAFFIC CONTROL SCHEDULE**

LOCATION	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
STATION	SIDE			
247+12.65	LT			1
247+12.65	RT		1	
247+39.48 TO 251+64.48	LT	425		
247+39.48 TO 251+64.48	RT	425		
251+91.30	LT		1	
251+91.30	RT		1	
TOTAL		425	2	2
PAY TOTAL		425	2	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP 317 (US ROUTE 24)  
 SECTION 25 RS-2 & 26 RS-4  
 LIVINGSTON COUNTY  
 SCALE: \_\_\_\_\_ DRAWN BY BANDY  
 DATE \_\_\_\_\_ CHECKED BY STEUART