

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517	IN	MCLEAN	21	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	AGGREGATE (PRIME COAT) (TON)	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70 (TON)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D" N 70 (TON)	BITUMINOUS SURFACE REMOVAL-BUTT JOINT (SQ YDS)	BITUMINOUS SHOULDERS SUPERPAVE 5 1/2" (SQ YDS)	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2" (SQ YDS)	AGGREGATE SHOULDERS, TYPE B (TONS)	BITUMINOUS BASE COURSE SUPERPAVE, 5 3/4" (SQ YD)
U.S. 150 WEST LEG	223	5	185	276	174	510	0	234	0
U.S. 150 EAST LEG	195	5	161	243	174	453	0	208	0
T.R. 328 NORTH LEG	42	1	6	75	0	0	112	21	765
T.R. 328 SOUTH LEG	61	2	46	54	0	0	105	0	0
TOTALS	521	13	398	648	348	963	217	463	765

LOCATION STATION	REMOVE EXISTING CULVERTS (EACH)	TRENCH BACKFILL (CU YD)	REMARKS
T.R. 328 9+83.3 2.6' LT	1	13.3	18 INCH CMP, 65 FEET
T.R. 328 10+70.7 2.6 LT	1	10.5	18 INCH CMP, 66 FEET
T.R. 328 11+95.3 14.6 LT	1		15 INCH CMP, 33 FEET
U.S. 150 383+78.6 30.7 RT	1		15 INCH CMP, 54 FEET
TOTAL	4	* 23.8	

* SUBTOTAL

LOCATION STA TO STA	SUB-BASE GRANULAR MATERIAL, TYPE A 4" (SQ YD)	STRIP REFLECTIVE CRACK CONTROL TREATMENT (FOOT)	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE, 10 1/2" (SQ YD)	BITUMINOUS BASE COURSE WIDENING, SUPERPAVE, 4 3/4" (SQ YD)
U.S. 150 WEST LEG	772	1506	727	0
U.S. 150 EAST LEG	771	1300	630	0
T.R. 328 SOUTH LEG	211	0	0	203
T.R. 328 NORTH LEG	790	0	0	0
TOTAL	2544	2806	1357	203

LOCATION STA TO STA	TREE REMOVAL 6 TO 15 UNITS DIAMETER UNIT	TREE REMOVAL OVER 15 UNITS DIAMETER UNIT
U.S. 150 385+28/73 RT	11	
U.S. 150 385+28/73 RT	7	
U.S. 150 385+53/115 RT		18
TOTAL	18	18

LOCATION STA TO STA	HEAVY DUTY EXCELSIOR BLANKET (SQ YD)	EXCELSIOR BLANKET, SPECIAL (SQ YD)	EROSION CONTROL BLANKET (SQ YD)	INLET AND PIPE PROTECTION (EACH)	TEMPORARY DITCH CHECKS (EACH)
U.S. 150 WEST LEG	0	0	3063	1	18
U.S. 150 EAST LEG	1745	1351	0	0	18
T.R. 328 SOUTH LEG	0	0	482	1	0
T.R. 328 NORTH LEG	0	0	245	2	0
TOTAL	1745	1351	3790	4	36

LOCATION STATION	PIPE CULVERTS, TYPE 1, CORR. STEEL OR ALUM. CULVERT PIPE 12" (FOOT)	STEEL END SECTIONS 12" (EACH)	PIPE CULVERTS, TYPE 1, CORR. STEEL OR ALUM. CULVERT PIPE 15" (FOOT)	STEEL END SECTIONS 15" (EACH)	PIPE CULVERTS, TYPE 1, CORR. STEEL OR ALUM. CULVERT PIPE 18" (FOOT)	STEEL END SECTIONS 18" (EACH)	TRENCH BACKFILL (CU YD)
T.R. 328 11+95, LT	28	2					
T.R. 328 10+82, CL					90	2	20.6
T.R. 328 9+62, CL					90	2	10.9
U.S. 150 383+71, 40' RT			36	2			
TOTAL	28	2	36	2	180	4	* 31.5

* SUBTOTAL

LOCATION STATION	AGGREGATE SURFACE COURSE TYPE B (TONS)
U.S. 150 383+71.3/30.6RT	38
T.R. 328 11+95/LT	18
T.R. 328 12+08/RT	18
TOTAL	74

LOCATION STA TO STA	DISTANCE (FEET)	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
U.S. 150 377+50 TO 385+00	750	842	632	632	0
U.S. 150 385+50 TO 392+00	650	859	644	574	70
T.R. 328 8+50 TO 10+00	150	191	143	1	142
T.R. 328 11+00 TO 13+00	200	643	482	0	482
TOTAL	1750	2535	1901	1207	695

COLUMN 4 = EARTH EXCAVATION ADJUSTED USING SHRINKAGE FACTOR OF 25%

LOCATION STATION	CLASS D PATCHES TYPE II 4 3/4" (SQ YD)
U.S. 150 385+50, 40' RT	5
U.S. 150 385+50, 40' RT	5
U.S. 150 385+50, 58' RT	8
U.S. 150 385+50, 58' RT	8
TOTAL	26

LOCATION U.S. 150 STA 377+56 TO STA 391+59	SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)	TEMPORARY EROSION CONTROL SEEDING (POUND)
TOTALS	2.00	180	180	180	0.75	400

LOCATION STA TO STA	THERMOPLASTIC MARKING SCHEDULE							RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
	LETTERS AND SYMBOLS WHITE (SQ FT)	LINE 4 INCH YELLOW (FOOT)	LINE 4 INCH WHITE (FOOT)	LINE 6 INCH WHITE (FOOT)	LINE 8 INCH WHITE (FOOT)	LINE 12 INCH WHITE (FOOT)	LINE 24 INCH WHITE (FOOT)		
T.R. 328 9+80 RT							43		
T.R. 328 10+70 LT							40		
T.R. 328 9+00 TO 12+50			630	80					
U.S. 150 377+56 TO 381+10						130			
U.S. 150 377+56 TO 391+59	78	5398	2652	250				75	17
U.S. 150 380+58 TO 384+58					266				
U.S. 150 386+60 TO 389+55					161				
U.S. 150 387+10 TO 391+59						148			
SUBTOTALS	78	5398	3282	330	427	278	83	75	17
TOTALS	78	8680	330	427	278	83	75	17	

LOCATION STA TO STA	SHORT TERM PAVEMENT MARKING (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
U.S. 150 377+56 TO 391+59	1146	191
T.R. 328 10+80 TO 12+50	34	6
T.R. 328 9+00 TO 10+07.5	22	3
TOTAL	1202	200

LOCATION STATION	PC	PT
380+47.83	1	
390+64.83		1
TOTAL	1	1

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY: