

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE TYPE:			
			90%FED 10%STATE TOTAL QUANTITY	LIGHTING Y030-1E	SIGNALS Y031-1F	ROADWAY I000-1A
20200100	EARTH EXCAVATION	CU YD	4572			4572
20400800	FURNISHED EXCAVATION	CU YD	846			846
20800150	TRENCH BACKFILL	CU YD	36			36
25000210	SEEDING, CLASS 2A	ACRE	0.97			0.97
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	87.3			87.3
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	87.3			87.3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	87.3			87.3
25100115	MULCH, METHOD 2	ACRE	0.73			0.73
25100630	EROSION CONTROL BLANKET	SQ YD	1164			1164
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	582			582
28000300	TEMPORARY DITCH CHECKS	EACH	6			6
28000500	INLET AND PIPE PROTECTION	EACH	1			1
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	744			744
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	379.5			379.5
40600300	AGGREGATE (PRIME COAT)	TON	9.5			9.5
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1.4			1.4
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	640			640
40600990	TEMPORARY RAMP	SQ YD	53.2			53.2
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	20			20
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30.4			30.4
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	673.3			673.3
50104300	CONCRETE HEADWALL REMOVAL	CU YD	13.8			13.8
50104400	CONCRETE HEADWALL REMOVAL	EACH	2			2
50800105	REINFORCEMENT BARS	POUND	652			652
54002020	EXPANSION BOLTS 3/4 INCH	EACH	64			64
54021003	PRECAST CONCRETE BOX CULVERT 10' X 3' (M273)	FOOT	83			83
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	77			77
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2			2
54248500	CONCRETE HEADWALLS	CU YD	9.2			9.2
54248510	CONCRETE COLLAR	CU YD	1.28			1.28
60100915	PIPE DRAINS 6"	FOOT	20			20
60625800	ISLAND PAVEMENT (SPECIAL)	SQ YD	95.7			95.7
61100605	MISCELLANEOUS CONCRETE	CU YD	0.5			0.5
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	15			15
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	4			4
67100100	MOBILIZATION	L SUM	1			1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1			1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1			1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1			1
70103815	TRAFFIC CONTROL AND SURVEILLANCE	CAL DA	35			35
70300100	SHORT-TERM PAVEMENT MARKING	FCOT	1432			1432
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FCOT	2920			2920
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FCOT	696			696
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FCOT	705			705
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FCOT	120			120

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	118 N	IROQUOIS	30	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
HORIZ.

DRAWN BY
CHECKED BY