

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	118 N	IROQUOIS	30	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SIGN SCHEDULE

LOCATION	TYPE	SIGN PANEL TYPE 1	WOOD SIGN SUPPORT	CONCRETE FOUNDATIONS	REMOVE SIGN PANEL ASSEMBLY	RELOCATE SIGN PANEL ASSEMBLY	PORTABLE CHANGEABLE MESSAGE SIGN
STA. OFFSET		SQ FT	FOOT	CU YD	EACH	EACH	EACH
STA 241+41, 49' LT	RI-1 (30X30)	6.25	10	0.3			
STA 241+51, 56' RT	RI-1 (30X30)	6.25	10	0.3			
STA 241+74, 26' RT	RI-1 (30X30)	6.25	10	0.3			
STA 241+74, 25' LT	RI-1 (30X30)	6.25	10	0.3			
STA 242+25, 25' LT	RI-1 (30X30)	6.25	10	0.3			
STA 242+25, 27' RT	RI-1 (30X30)	6.25	10	0.3			
STA 242+49, 55' LT	RI-1 (30X30)	6.25	10	0.3			
STA 242+59, 50' RT	RI-1 (30X30)	6.25	10	0.3			
STA 241+40, 29' RT			10	0.3			
STA 241+40, 31' RT			10	0.3			
STA 241+40, 33' RT			10	0.3			
STA 242+57, 26' LT			10	0.3			
STA 242+57, 28' LT			10	0.3			
STA 242+57, 30' LT			10	0.3			
STA 231+12, 25' LT					1		
STA 231+12, 25' RT					1		
STA 252+88, 22' LT					1		
STA 252+88, 22' RT					1		
STA 241+40, 26' LT	RI-1 (30X30)				1		
STA 241+40, 25' RT	RI-1 (30X30)				1		
STA 242+57, 22' LT	RI-1 (30X30)				1		
STA 242+57, 25' RT	RI-1 (30X30)				1		
STA 237+24, 18' LT	W3-1 (36X36)	9	10	0.3			
STA 237+24, 18' RT	W3-1 (36X36)	9	10	0.3			
STA 817+77, 19' LT	W3-1 (36X36)	9	10	0.3			
STA 817+77, 19' RT	W3-1 (36X36)	9	10	0.3			
STA 827+38, 19' LT	W3-1 (36X36)	9	10	0.3			
STA 827+38, 19' RT	W3-1 (36X36)	9	10	0.3			
STA 246+75, 17' LT	W3-1 (36X36)	9	10	0.3			
STA 246+75, 17' RT	W3-1 (36X36)	9	10	0.3			
TOTAL		122	220	6.6	8	6	2

* YELLOW FLASHING BEACONS MOUNTED ACCORDING TO LIGHTING DETAIL

THERMOPLASTIC PAVEMENT MARKINGS

LOCATION	LENGTH	THERMO PVMT MK MARKING LINE 4"	THERMO PVMT MK MARKING LINE 8"	THERMO PVMT MK MARKING LINE 12"		THERMO PVMT MK MARKING LINE 24"
		YELLOW	WHITE	WHITE	YELLOW	YELLOW
	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT
IROQUOIS COUNTY						
STA 239+00 TO STA 240+00	100	200				
STA 240+00 TO STA 240+55	55.0	110				
STA 240+55 TO STA 241+55	100.0	400			16.1	
STA 241+55 TO STA 242+45	90.0	40				
STA 242+45 TO STA 243+45	100.0	400			15.8	
STA 243+45 TO STA 244+00	55.0	110				
STA 244+00 TO STA 245+00	100.0	200				
STA 819+50 TO STA 820+50	100.0	200				
STA 820+50 TO STA 821+10	60.0	120				
STA 821+10 TO STA 822+10	100.0	400			16.0	
STA 822+10 TO STA 823+00	90.0	40				
STA 823+00 TO STA 824+00	100.0	400			15.8	
STA 824+00 TO STA 824+50	50.0	100				
STA 824+50 TO 825+50	100.0	200				
NW ISLAND			171		160	
NE ISLAND			169		156	
SE ISLAND			186		165	
SW ISLAND			170		160	
* STOP BARS						120
TOTAL	1200.0	2920	696	641	64	120

* SEE PAVEMENT MARKING SHEET FOR LOCATIONS OF STOP BARS

DRAINAGE SCHEDULE

STATION	INFLOW ELEVATION	OUTFLOW ELEVATION	GRADE	CONCRETE HEADWALLS	FILLING EXISTING CULVERTS	CONCRETE COLLAR	EXPANSION BOLTS 3/4" DIA.	MISCELLANEOUS CONCRETE	PIPE DRAIN 6"	REINFORCEMENT BARS	CONCRETE HEADWALL REMOVAL	TRENCH BACKFILL	CONCRETE HEADWALL REMOVAL	PRECAST CONCRETE BOX CULVERT M 273 10' X 3'	PIPE CULVERT CLASS A TYPE 2, 18"	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"
			%	CU YD	EACH	CU YD	EACH	CU YD	FOOT	LBS	EACH	CU YD	CU YD	FOOT	FOOT	EACH
241+00	629.70	629.20	0.56													
241+50					1							36			77	2
822+00 RT	629.18		0.28	4.6		0.64	32			326	2		4.6	39		
822+00 LT		628.77		4.6		0.64	32			326			9.2	44		
FIELD TILE CONTINGENCY ITEMS																
TOTAL				9.2	1	1.28	64	0.5	20	652	2	36	13.8	83	77	2

TEMPORARY PAVEMENT MARKINGS

LOCATION	LENGTH	TEMPORARY PVMT MK MARKING LINE 4"	TEMPORARY PVMT MK MARKING LINE 8"	TEMPORARY PVMT MK MARKING LINE 12"		TEMPORARY PVMT MK MARKING LINE 24"	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVT MARKING REMOVAL
		YELLOW	WHITE	WHITE	YELLOW	YELLOW	YELLOW	SQ FT
	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	
IROQUOIS COUNTY								
STA 239+00 TO STA 240+00	100.0	200					40	6.7
STA 240+00 TO STA 240+55	55.0	110					22	3.7
STA 240+55 TO STA 241+55	100.0	400				16.1	80	13.3
STA 241+55 TO STA 242+45	90.0	40					72	12.0
STA 242+45 TO STA 243+45	100.0	400				15.8	80	13.3
STA 243+45 TO STA 244+00	55.0	110					22	3.7
STA 244+00 TO STA 245+00	100.0	200					40	6.7
STA 819+50 TO STA 820+50	100.0	200					40	6.7
STA 820+50 TO STA 821+10	60.0	120					24	4.0
STA 821+10 TO STA 822+10	100.0	400				16.0	80	13.3
STA 822+10 TO STA 823+00	90.0	40					72	12.0
STA 823+00 TO STA 824+00	100.0	400				15.8	80	13.3
STA 824+00 TO STA 824+50	50.0	100					20	3.3
STA 824+50 TO 825+50	100.0	200					40	6.7
NW ISLAND			171		160			
NE ISLAND			169		156			
SE ISLAND			186		165			
SW ISLAND			170		160			
STOP BARS							120.0	720
TOTAL	1200.0	2920	696	641	64	120	1432	238

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY