

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	54
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

	STA	OFFSET	PERMANENT SURVEY MARKERS - TYPE II	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	FURNISHING AND ERECTING RIGHT OF WAY MARKERS WMD/OTHER STS	
			FA	EACH	EACH	
Sterling	100+098.176	63.414 M RT			1	
	100+095.132	66.367 M RT			1	
	100+092.114	32.322 M RT			1	
	100+082.005	14.649 M RT			1	
Scenic	010+119.856	25.156 M RT			1	
	010+124.586	25.181 M RT			1	
	010+137.026	18.288 M RT			1	
	010+174.850	20.513 M RT			1	
	010+199.167	24.533 M RT			1	
	143+148.984	49.757 M LT		1		
	143+149.087	48.333 M LT		1		
	143+203.309	55.375 M LT		1		
	143+205.124	57.691 M LT		1		
	143+204.673	70.462 M LT		1		
	143+234.998	82.900 M LT		1		
WMD	143+254.335	77.664 M LT		1		
	143+279.188	60.198 M LT		1		
	143+303.688	58.321 M LT		1		
	143+421.987	64.791 M LT		1		
	143+436.748	99.099 M LT		1		
	100+885.221	63.243 M RT			1	
	100+889.367	73.538 M RT			1	
	100+928.850	73.462 M RT			1	
	100+929.365	68.456 M RT			1	
	RAMP 1 AT WMD	N451492.7934	E746040.0019	1	11	13
	TOTAL			1000-2A	1000-2A	1000-2A

LOCATIONS	STA	TO	STA	WATER (DUST CONTROL)	APPLY DUST SUPPRESSION AGENTS	SOIL STABILIZERS	STREET SWEEPING	DUST CONTROL PADS
	FAI ROUTE 74 (WESTBOUND)			UNITS	UNITS	KG	HOUR	EACH
				2000gal/ap X3.8 L/gal/1000		2 App X2250kg/ha		
I-74 MAINLINE, WB	141+900.000	TO	144+325.000	395	988	60,750	122	1
RAMP A -3	10+000.000	TO	10+700.000			3,645	50	
RAMP A -4	10+345.280	TO	10+635.280					
RAMP B-1	10+137.970	TO	11+143.980			4,545	50	
RAMP B-2	10+192.810	TO	10+753.821			3,780	50	
RAMP B-3	10+000.000	TO	11+156.310			7,020	50	
RAMP B-4	10+012.490	TO	11+044.450			3,645	50	
RAMP B-5	10+019.180	TO	11+093.960			4,635	50	1
RAMP B-6	10+020.730	TO	10+203.450			383	20	
WM DRIVE	38+965.070	TO	40+480.820					
I-74 MAINLINE, WB	144+325.000	TO	144+718.000			7,740	40	
TOTAL (1000-2A)				395	988	96,143	482	2

STA	LOCATION	Size	Number	Plus 30 %			CLASS B PATCHES, TYPE II, 250 MM	DOWEL BARS 38 MM	SAW CUTS
				Area/Each	Dowels/Each	Saw Cuts/Each			
				SQ M	Each	Meter	SQ M	EACH	METER
	WMD Westbound	3.6M X 1.8M	74	6.48	20	14.4	480.168	1,482	1,067
	WMD Eastbound	3.6M X 1.8M	44	6.48	20	14.4	286.416	884	636
SUBTOTAL			118				767	2,366	1,704
TOTALS	1000-2A						767	2,366	1,704

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**RIGHT OF WAY**  
 FAI ROUTE 74 (I-74) (WB)  
**DUST CONTROL & PATCHES**  
 DRAWN BY CADD  
 CHECKED BY RSC  
 DATE 11/12/04

