


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-71R-3)	PEORIA	1360	83
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TEMPORARY PAVEMENT SCHEDULE										
LOCATION				LENGTH	WIDTH	AREA (CADD CALCS)	TEMPORARY PAVEMENT	TEMPORARY PAVEMENT REMOVAL		
STA	TO	STA		M	M	SQ M	SQ M	SQ M		
STAGE 3-1										
RAMP A-4		142+350.000		142+660.000		65.50	65.50			
RAMP A-4 STAGING						50.00	50.00			
SCENIC DRIVE		10+050.000		10+245.000		141.36	141.36			
TCIS RAMP B1		10+250.000		10+450.000		1,079.49		1,079.49		
RAMP B-1		10+137.966		10+219.480		394.64		394.64		
RAMP B-4		10+925.000		10+972.450		240.07		240.07		
SUBTOTAL STAGE 3-1							256.86	1,714.20		
STAGE 3-2										
RAMP A-4		142+350.000		142+660.000		1,654.90		1,654.90		
RAMP A-4 STAGING						50.00		50.00		
SUBTOTAL STAGE 3-2							0.00	1,704.90		
STAGE 3-3										
SCENIC DRIVE		10+050.000		10+245.000		141.36		141.36		
SUBTOTAL STAGE 3-3							0.00	141.36		
STAGE 3-4										
RAMP A-4 CROSSOVER		142+335.000		142+425.000		715.12		715.12		
RAMP A-3		142+961.000		143+155.000		1,031.63		1,031.63		
RAMP A-3 CROSSOVER		143+181.000		143+323.000		117.59		117.59		
SHOULDER, TCIS BTW B-1/B-4		143+800.000		144+175.000		1,170.66		1,170.66		
SUBTOTAL STAGE 3-4							0.00	3,035.00		
TOTALS							256.86	6,595.46		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 TEMPORARY PAVEMENT
 FAI ROUTE 74 (I-74) (WB)
 SCHEDULES

DATE 11/12/04
 DRAWN BY CADD
 CHECKED BY RSC



11/12/04 11:23 AM