

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	86
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY PAVEMENT MARKING SCHEDULE										
FAI ROUTE 74					TEMPORARY PAVEMENT MARKING TAPE, TYPE III					WET TEMPORARY PAVEMENT MARKING TAPE TYPE III
					100 MM WHITE SOLID	100 MM YELLOW SOLID	100 MM WHITE SKIP-DASH	100 MM YELLOW SKIP-DASH	200 MM WHITE SOLID	100 MM WHITE SOLID
LOCATIONS	STATION	TO	STATION	LENGTH	M	M	M	M	M	M
				STAGE 3-2						
I-74 MAINLINE,	141+250.000	TO	141+600.000							
	141+413		141+450	37.0	37.0					
	141+413		141+600	187.0	187.0					
	141+450		141+600	150.0		150.0				
I-74 MAINLINE,	141+600.000	TO	141+950.000							
	141+600		141+950	350.0	350.0	350.0				
I-74 MAINLINE,	141+950.000	TO	142+300.000							
	141+950		142+300	350.0	350.0	350.0				
	142+200		142+300	100.0	100.0	100.0				
I-74 MAINLINE,	142+300.000	TO	142+650.000							
	142+300		142+640	340.0	340.0	340.0				
	142+300		142+640	340.0	340.0	340.0				
	142+300		142+650	350.0	350.0	350.0				
I-74 MAINLINE,	142+650.000	TO	143+000.000							
	142+650		142+659	9.0	9.0	9.0				
I-74 MAINLINE,	143+000.000	TO	143+300.000							
I-74 MAINLINE,	143+300.000	TO	143+650.000							
I-74 MAINLINE,	143+650.000	TO	143+950.000							
I-74 MAINLINE,	143+950.000	TO	144+250.000							
I-74 MAINLINE,	144+250.000	TO	144+325.000							
I-74 MAINLINE,	144+325.000	TO	144+600.000							
I-74 MAINLINE,	144+600.000	TO	144+718.000							
SUBTOTAL				I-74	2,063.0	1,989.0	0.0	0.0	0.0	0.0



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 TEMPORARY PAVEMENT MARKING
 FAI ROUTE 74 (I-74) (WB)
 SCHEDULES
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04